

PROFESSIONAL DESIGN SERVICES AGREEMENT

This PROFESSIONAL DESIGN SERVICES AGREEMENT, (hereinafter referred to as "Agreement"), is made and entered into to be effective the 22nd day of April, 2026 by and between the ORANGE COUNTY SANITATION DISTRICT, (hereinafter referred to as "OC SAN"), and Dudek, (hereinafter referred to as "CONSULTANT").

WITNESSETH:

WHEREAS, OC SAN desires to engage CONSULTANT for **MacArthur Pump Station Rehabilitation, Project No. 7-63**; and to provide professional design services to replace and rehabilitate existing pump station assets that are reaching their useful life, (Services) and

WHEREAS, CONSULTANT is qualified to provide the necessary services in connection with these requirements and has agreed to provide the necessary professional services; and

WHEREAS, OC SAN has adopted procedures for the selection of professional design services and has proceeded in accordance with said procedures to select CONSULTANT to perform the Services; and

WHEREAS, at its regular meeting on April 22, 2026 the Board of Directors, by Minute Order, accepted the recommendation of the Operations Committee pursuant to OC SAN's current Purchasing Ordinance to approve this Agreement.

NOW, THEREFORE, in consideration of the promises and mutual benefits, which will result to the parties in carrying out the terms of this Agreement, it is mutually agreed as follows:

1. SCOPE OF WORK

CONSULTANT agrees to furnish necessary professional and technical services to accomplish those project elements outlined in the Scope of Work attached hereto as Attachment "A", and by this reference made a part of this Agreement.

- A. The CONSULTANT shall be responsible for the professional quality, technical accuracy, completeness, and coordination of all design, drawings, specifications, and other services furnished by the CONSULTANT under this Agreement, including the work performed by its subconsultants (Subconsultants). Where approval by OC SAN is indicated, it is understood to be conceptual approval only and does not relieve the CONSULTANT of responsibility for complying with all laws, codes, industry standards, and liability for damages caused by errors, omissions, noncompliance with industry standards, and/or negligence on the part of the CONSULTANT or its Subconsultants.
- B. CONSULTANT is responsible for the quality of work prepared under this Agreement and shall ensure that all work is performed to the standards of best engineering practice for clarity, uniformity, and completeness. CONSULTANT shall respond to all of OC SAN's questions, comments, suggestions, corrections, and recommendations (i.e., DS1, DS2, DS3, and FDS). All comments shall be incorporated into the design prior to the next submittal deadline or addressed, in

writing, as to why the comment has not been incorporated. CONSULTANT shall ensure that each submittal is 100% accurate for the level of work submitted (i.e., correct references, terms, capitalization, or equal status, spelling, punctuation, etc.)

- C. In the event that work is not performed to the reasonable satisfaction of OC SAN and does not conform to the requirements of this Agreement or any applicable industry standards, the CONSULTANT shall, without additional compensation, promptly correct or revise any errors or deficiencies in its designs, drawings, specifications, or other services within the timeframe specified by the Project Engineer/Project Manager. OC SAN may charge to CONSULTANT all costs, expenses and damages associated with any such corrections or revisions.
- D. All CAD drawings, figures, and other work shall be produced by CONSULTANTS and Subconsultants using OC SAN CAD Manual. Conversion of CAD work from any other non-standard CAD format to OC SAN format shall not be acceptable in lieu of this requirement.

Electronic files shall conform to OC SAN specifications. Any changes to these specifications by the CONSULTANT are subject to review and approval of OC SAN.

Electronic files shall be subject to an acceptance period of 30 calendar days during which OC SAN shall perform appropriate reviews and including CAD Manual compliance. CONSULTANT shall correct any discrepancies or errors detected and reported within the acceptance period at no additional cost to OC SAN.

- E. The CONSULTANT shall ensure that all plans and specifications prepared or recommended under this Agreement allow for competitive bidding. The CONSULTANT shall design such plans or specifications so that procurement of services, labor or materials are not available from only one source, and shall not design plans and specifications around a single or specific product, piece of major equipment or machinery, a specific patented design or a proprietary process, unless required by principles of sound engineering practice and supported by a written justification that has been approved in writing by OC SAN. The CONSULTANT shall submit this written justification to OC SAN prior to beginning work on such plans and specifications. Whenever the CONSULTANT recommends a specific product or equipment for competitive procurement, such recommendation shall include at least two brand names of products that are capable of meeting the functional requirements applicable to the project.
- F. All professional services performed by the CONSULTANT, including but not limited to all drafts, data, correspondence, proposals, reports, and estimates compiled or composed by the CONSULTANT, pursuant to this Agreement, are for the sole use of OC SAN, its agents and employees. Neither the documents nor their contents shall be released to any third party without the prior written consent of OC SAN. This provision does not apply to information that (a) was publicly known, or otherwise known to the CONSULTANT, at the time that it was disclosed to the CONSULTANT by OC SAN, (b) subsequently becomes publicly known to the CONSULTANT other than through disclosure by OC SAN.

2. COMPENSATION

Total compensation shall be paid to CONSULTANT for the Services in accordance with the following provisions:

A. Total Compensation

Total compensation shall be in an amount not to exceed One Million One Hundred Forty Thousand Dollars (\$1,140,000). Total compensation to CONSULTANT including burdened labor (salaries plus benefits), overhead, profit, direct costs, and Subconsultant(s) fees and costs shall not exceed the sum set forth in Attachment "E" - Fee Proposal.

B. Labor

As a portion of the total compensation to be paid to CONSULTANT, OC SAN shall pay to CONSULTANT a sum equal to the burdened salaries (salaries plus benefits) actually paid by CONSULTANT charged on an hourly-rate basis to this project and paid to the personnel of CONSULTANT. Upon request of OC SAN, CONSULTANT shall provide OC SAN with certified payroll records of all employees' work that is charged to this project.

Direct Salary rates for CONSULTANT and its Subconsultants may be adjusted annually on January 1st by mutual agreement of the Parties. Escalation of the salary rate will be in accordance with Consumer Price Index of LA-Orange County Index. This rate is determined by the U.S. Department of Labor Statistics, Consumer Price Index – Los Angeles/ Orange County Metropolitan Area.

C. Overhead

As a portion of the total compensation to be paid to CONSULTANT, OC SAN shall compensate CONSULTANT and Subconsultants for overhead at the rate equal to the percentage of burdened labor as specified in Attachment "E" - Fee Proposal.

D. Profit

Profit for CONSULTANT and Subconsultants shall be a percentage of consulting services fees (Burdened Labor and Overhead). When the consulting or subconsulting services amount is \$250,000 or less, the maximum Profit shall be 10%. Between \$250,000 and \$2,500,000, the maximum Profit shall be limited by a straight declining percentage between 10% and 5%. For consulting or subconsulting services fees with a value greater than \$2,500,000, the maximum Profit shall be 5%. Addenda shall be governed by the same maximum Profit percentage after adding consulting services fees.

As a portion of the total compensation to be paid to CONSULTANT and Subconsultants, OC SAN shall pay profit for all services rendered by

CONSULTANT and Subconsultants for this project according to Attachment "E" - Fee Proposal.

E. Subconsultants

For any Subconsultant whose fees for services are greater than or equal to \$100,000 (excluding out-of-pocket costs), CONSULTANT shall pay to Subconsultant total compensation in accordance with the Subconsultant amount specified in Attachment "E" - Fee Proposal.

For any Subconsultant whose fees for services are less than \$100,000, CONSULTANT may pay to Subconsultant total compensation on an hourly-rate basis per the attached hourly rate Schedule and as specified in the Scope of Work. OC SAN shall pay to CONSULTANT the actual costs of Subconsultant fees and charges in an amount not to exceed the sum set forth in Attachment "E" - Fee Proposal.

F. Direct Costs

OC SAN shall pay to CONSULTANT and Subconsultants the actual costs of permits and associated fees, travel and licenses for an amount not to exceed the sum set forth in Attachment "E" - Fee Proposal. OC SAN shall also pay to CONSULTANT actual costs for equipment rentals, leases or purchases with prior approval of OC SAN. Upon request, CONSULTANT shall provide to OC SAN receipts and other documentary records to support CONSULTANT's request for reimbursement of these amounts, see Attachment "D" - Allowable Direct Costs. All incidental expenses shall be included in overhead pursuant to Section 2 - COMPENSATION above.

G. Other Direct Costs

Other Direct Costs incurred by CONSULTANT and its Contractor due to modifications to the Scope of Work resulting from field investigations and field work required by the Agreement. These items may include special equipment, test equipment and tooling and other materials and services not previously identified. Refer to attachment "D" Allowable Direct Costs for payment information.

H. Reimbursable Direct Costs

OC SAN will reimburse the CONSULTANT for reasonable travel and business expenses as described in this section and further described in Attachment "D" - Allowable Direct Costs to this Agreement. The reimbursement of the above-mentioned expenses will be based on an "accountable plan" as considered by Internal Revenue Service (IRS). The plan includes a combination of reimbursements based upon receipts and a "per diem" component approved by IRS. The most recent schedule of the per diem rates utilized by OC SAN can be found on the U.S. General Service Administration website at <https://www.gsa.gov/travel/plan-book/per-diem-rates>.

The CONSULTANT shall be responsible for the most economical and practical means of management of reimbursable costs inclusive but not limited to travel, lodging and meals arrangements. OC SAN shall apply the most economic and practical method of reimbursement which may include reimbursements based upon receipts and/or “per diem” as deemed the most practical.

CONSULTANT shall be responsible for returning to OC SAN any excess reimbursements after the reimbursement has been paid by OC SAN.

Travel and travel arrangements – Any travel involving airfare, overnight stays or multiple day attendance must be approved by OC SAN in advance.

Local Travel is considered travel by the CONSULTANT within OC SAN general geographical area which includes Orange, Los Angeles, Ventura, San Bernardino, Riverside, San Diego, Imperial, and Kern Counties. Automobile mileage is reimbursable if CONSULTANT is required to utilize personal vehicle for local travel.

Lodging – Overnight stays will not be approved by OC SAN for local travel. However, under certain circumstances overnight stay may be allowed at the discretion of OC SAN based on reasonableness of meeting schedules and the amount of time required for travel by the CONSULTANT. Such determination will be made on a case-by-case basis and at the discretion of OC SAN.

Travel Meals – Per-diem rates as approved by IRS shall be utilized for travel meals reimbursements. Per diem rates shall be applied to meals that are appropriate for travel times. Receipts are not required for the approved meals.

Additional details related to the reimbursement of the allowable direct costs are provided in the Attachment “D” - Allowable Direct Costs of this Agreement.

I. Limitation of Costs

If, at any time, CONSULTANT estimates the cost of performing the services described in CONSULTANT’s Proposal will exceed seventy-five percent (75%) of the not-to-exceed amount of the Agreement, including approved additional compensation, CONSULTANT shall notify OC SAN immediately, and in writing. This written notice shall indicate the additional amount necessary to complete the services. Any cost incurred in excess of the approved not-to-exceed amount, without the express written consent of OC SAN’s authorized representative shall be at CONSULTANT’s own risk. This written notice shall be provided separately from, and in addition to any notification requirements contained in the CONSULTANT’s invoice and monthly progress report. Failure to notify OC SAN that the services cannot be completed within the authorized not-to-exceed amount is a material breach of this Agreement.

3. REALLOCATION OF TOTAL COMPENSATION

OC SAN, by its Director of Engineering, shall have the right to approve a reallocation of the incremental amounts constituting the total compensation, provided that the total compensation is not increased.

4. PAYMENT

- A. Monthly Invoice: CONSULTANT shall include in its monthly invoice, a detailed breakdown of costs associated with the performance of any corrections or revisions of the work for that invoicing period. CONSULTANT shall allocate costs in the same manner as it would for payment requests as described in this Section of the Agreement. CONSULTANT shall warrant and certify the accuracy of these costs and understand that submitted costs are subject to Section 11 - AUDIT PROVISIONS.
- B. CONSULTANT may submit monthly or periodic statements requesting payment for those items included in Section 2 - COMPENSATION hereof in the format as required by OC SAN. Such requests shall be based upon the amount and value of the work and services performed by CONSULTANT under this Agreement and shall be prepared by CONSULTANT and accompanied by such supporting data, including a detailed breakdown of all costs incurred and work performed during the period covered by the statement, as may be required by OC SAN.

Upon approval of such payment request by OC SAN, payment shall be made to CONSULTANT within thirty (30) days of invoice receipt of one hundred percent (100%) of the invoiced amount on a per task basis.

If OC SAN determines that the work under this Agreement, or any specified task hereunder, is incomplete and that the amount of payment is in excess of:

- i. The amount considered by OC SAN's Director of Engineering to be adequate for the protection of OC SAN; or
- ii. The percentage of the work accomplished for each task.

OC SAN may, at the discretion of the Director of Engineering, retain an amount equal to that which ensures that the total amount paid to that date does not exceed the percentage of the completed work for each task or the project in its entirety.

- C. CONSULTANT may submit periodic payment requests for each 30-day period of this Agreement for the profit as set forth in Section 2 - COMPENSATION above. Said profit payment request shall be proportionate to the work actually accomplished to date on a per task basis. In the event OC SAN's Director of Engineering determines that no satisfactory progress has been made since the prior payment, or in the event of a delay in the work progress for any reason, OC SAN shall have the right to withhold any scheduled proportionate profit payment.
- D. Upon satisfactory completion by CONSULTANT of the work called for under the terms of this Agreement, and upon acceptance of such work by OC SAN, CONSULTANT will be paid the unpaid balance of any money due for such work, including any retained percentages relating to this portion of the work.

- E. Upon satisfactory completion of the work performed hereunder and prior to final payment under this Agreement for such work, or prior settlement upon termination of this Agreement, and as a condition precedent thereto, CONSULTANT shall execute and deliver to OC SAN a release of all claims against OC SAN arising under or by virtue of this Agreement other than such claims, if any, as may be specifically exempted by CONSULTANT from the operation of the release in stated amounts to be set forth therein.
- F. Pursuant to the California False Claims Act (Government Code Sections 12650-12655), any CONSULTANT that knowingly submits a false claim to OC SAN for compensation under the terms of this Agreement may be held liable for treble damages and up to a ten thousand dollars (\$10,000) civil penalty for each false claim submitted. This Section shall also be binding on all Subconsultants.

A CONSULTANT or Subconsultant shall be deemed to have submitted a false claim when the CONSULTANT or Subconsultant: a) knowingly presents or causes to be presented to an officer or employee of OC SAN a false claim or request for payment or approval; b) knowingly makes, uses, or causes to be made or used a false record or statement to get a false claim paid or approved by OC SAN; c) conspires to defraud OC SAN by getting a false claim allowed or paid by OC SAN; d) knowingly makes, uses, or causes to be made or used a false record or statement to conceal, avoid, or decrease an obligation to OC SAN; or e) is a beneficiary of an inadvertent submission of a false claim to OC SAN, and fails to disclose the false claim to OC SAN within a reasonable time after discovery of the false claim.

5. CALIFORNIA DEPARTMENT OF INDUSTRIAL RELATIONS (DIR) REGISTRATION AND RECORD OF WAGES

- A. To the extent CONSULTANT's employees and/or Subconsultants who will perform work during the design and preconstruction phases of a construction contract for which Prevailing Wage Determinations have been issued by the DIR and as more specifically defined under Labor Code Section 1720 et seq, CONSULTANT and Subconsultants shall comply with the registration requirements of Labor Code Section 1725.5. Pursuant to Labor Code Section 1771.4, the work is subject to compliance monitoring and enforcement by the DIR.
- B. The CONSULTANT and Subconsultants shall maintain accurate payroll records and shall comply with all the provisions of Labor Code Section 1776, and shall submit payroll records to the Labor Commissioner pursuant to Labor Code Section 1771.4(a)(3). Penalties for non-compliance with the requirements of Section 1776 may be deducted from progress payments per Section 1776.
- C. Pursuant to Labor Code Section 1776, the CONSULTANT and Subconsultants shall furnish a copy of all certified payroll records to OC SAN and/or general public upon request, provided the public request is made through OC SAN, the Division of Apprenticeship Standards or the Division of Labor Enforcement of the Department of Industrial Relations.

- D. The CONSULTANT and Subconsultants shall comply with the job site notices posting requirements established by the Labor Commissioner per Title 8, California Code of Regulation Section 16461(e).

6. DOCUMENT OWNERSHIP – SUBSEQUENT CHANGES TO PLANS AND SPECIFICATIONS

- A. Ownership of Documents for the Services performed.

Upon full payment to CONSULTANT for Services rendered, all documents, including but not limited to, original plans, studies, sketches, drawings, computer printouts and disk files, and specifications prepared in connection with or related to the Scope of Work or Services, shall be the property of OC SAN. OC SAN's ownership of these documents includes use of, reproduction or reuse of and all incidental rights, whether or not the work for which they were prepared has been performed. OC SAN ownership entitlement arises upon payment for work performed and includes ownership of any and all work product completed prior to that payment. This Section shall apply whether the CONSULTANT's Services are terminated: a) by the completion of the Agreement, or b) in accordance with other provisions of this Agreement. Notwithstanding any other provision of this paragraph or Agreement, the CONSULTANT shall have the right to make copies of all such plans, studies, sketches, drawings, computer printouts and disk files, and specifications.

- B. CONSULTANT shall not be responsible for damage caused by subsequent changes to or uses of the plans or specifications, where the subsequent changes or uses are not authorized or approved by CONSULTANT.

7. INSURANCE

- A. General

- i. Insurance shall be issued and underwritten by insurance companies acceptable to OC SAN.
- ii. Insurers must have an "A-" Policyholder's Rating, or better, and Financial Rating of at least Class VIII, or better, in accordance with the most current A.M. Best's Guide Rating. However, OC SAN will accept State Compensation Insurance Fund, for the required policy of Workers' Compensation Insurance subject to OC SAN's option to require a change in insurer in the event the State Fund financial rating is decreased below "B". Further, OC SAN will require CONSULTANT to substitute any insurer whose rating drops below the levels herein specified. Said substitution shall occur within twenty (20) days of written notice to CONSULTANT, by OC SAN or its agent.
- iii. Coverage shall be in effect prior to the commencement of any work under this Agreement.

B. General Liability

The CONSULTANT shall maintain during the life of this Agreement, including the period of warranty, commercial general liability insurance written on an occurrence basis providing the following minimum limits of liability coverage: Two Million Dollars (\$2,000,000) per occurrence with Four Million Dollars (\$4,000,000) aggregate. If aggregate limits apply separately to this Agreement (as evidenced by submission of ISO form CG 25 03 or 25 04), then the aggregate limit may be equivalent to the per occurrence limit. Said insurance shall include coverage for the following hazards: premises-operations, blanket contractual liability (for this Agreement), products liability/completed operations (including any product manufactured or assembled), broad form property damage, blanket contractual liability, independent contractors liability, personal and advertising injury, mobile equipment, owners and contractors protective liability, and cross liability and severability of interest clauses. A statement on an insurance certificate will not be accepted in lieu of the actual additional insured endorsement(s). If requested by OC SAN and applicable, XCU coverage (Explosion, Collapse and Underground) and Riggers/On Hook Liability must be included in the general liability policy and coverage must be reflected on the submitted certificate of insurance. Where permitted by law, CONSULTANT hereby waives all rights of recovery by subrogation because of deductible clauses, inadequacy of limits of any insurance policy, limitations or exclusions of coverage, or any other reason against OC SAN, its or their officers, agents, or employees, and any other consultant, contractor, or subcontractor performing work or rendering services on behalf of OC SAN in connection with the planning, development, and construction of the project. In all its insurance coverages related to the work, CONSULTANT shall include clauses providing that each insurer shall waive all of its rights of recovery by subrogation against OC SAN, its or their officers, agents, or employees, or any other consultant, contractor, or subcontractor performing work or rendering services at the project. Where permitted by law, CONSULTANT shall require similar written express waivers and insurance clauses from each of its Subconsultants of every tier. A waiver of subrogation shall be effective as to any individual or entity, even if such individual or entity (a) would otherwise have a duty of indemnification, contractual or otherwise, (b) did not pay the insurance premium, directly or indirectly, and (c) whether or not such individual or entity has an insurable interest in the property damaged.

C. Automobile/Vehicle Liability Insurance

The CONSULTANT shall maintain a policy of automobile liability insurance on a comprehensive form covering all owned, non-owned, and hired automobiles, trucks, and other vehicles providing the following minimum limit of liability coverage: combined single limit of One Million Dollars (\$1,000,000). A statement on an insurance certificate will not be accepted in lieu of the actual additional insured endorsement.

D. Umbrella Excess Liability

The minimum limits of general liability and automobile liability insurance required, as set forth herein, shall be provided for through either a single policy of primary

insurance or a combination of policies of primary and umbrella excess coverage. Umbrella excess liability coverage shall be issued with limits of liability which, when combined with the primary insurance, will equal the minimum limits for general liability and automobile liability.

E. Workers' Compensation Insurance

The CONSULTANT shall provide such workers' compensation insurance as required by the Labor Code of the State of California in the amount of the statutory limit, including employer's liability insurance with a minimum limit of One Million Dollars (\$1,000,000) per occurrence. Such workers' compensation insurance shall be endorsed to provide for a waiver of subrogation in favor of OC SAN. A statement on an insurance certificate will not be accepted in lieu of the actual endorsements unless the insurance carrier is State of California Insurance Fund and the identifier "SCIF" and endorsement numbers 2570 and 2065 are referenced on the certificate of insurance. If an exposure to Jones Act liability may exist, the insurance required herein shall include coverage for Jones Act claims.

F. Errors and Omissions/Professional Liability

CONSULTANT shall maintain in full force and effect, throughout the term of this Agreement, standard industry form professional liability / errors and omissions insurance coverage with coverage limits of not less than Two Million Dollars (\$2,000,000) in accordance with the provisions of this paragraph. If the policy of insurance is written on a "claims made" basis, said policy shall be continued in full force and effect at all times during the term of this Agreement, and for a period of five (5) years from the date of the completion of the services hereunder.

In the event of termination of said policy during this period, CONSULTANT shall obtain continuing insurance coverage for the prior acts or omissions of CONSULTANT during the course of performing services under the terms of this Agreement. Said coverage shall be evidenced by either a new policy evidencing no gap in coverage or by separate extended "tail" coverage with the present or new carrier.

In the event the present policy of insurance is written on an "occurrence" basis, said policy shall be continued in full force and effect during the term of this Agreement or until completion of the services provided for in this Agreement, whichever is later. In the event of termination of said policy during this period, new coverage shall be obtained for the required period to insure for the prior acts or omissions of CONSULTANT during the course of performing services under the terms of this Agreement.

CONSULTANT shall provide to OC SAN a certificate of insurance in a form acceptable to OC SAN indicating the deductible or self-retention amounts and the expiration date of said policy and shall provide renewal certificates not less than ten (10) days prior to the expiration of each policy term.

G. Drone Liability Insurance

If a drone will be used, drone liability insurance must be maintained by CONSULTANT in the amount of One Million Dollars (\$1,000,000) in form acceptable to OC SAN.

H. Proof of Coverage

The CONSULTANT shall furnish OC SAN with original certificates and amendatory endorsements effecting coverage. Said policies and endorsements shall conform to the requirements herein stated. All certificates and endorsements are to be received and approved by OC SAN before work commences. OC SAN reserves the right to require, at any time, complete, certified copies of all required insurance policies, including endorsements, effecting the coverage required. The following are approved forms that must be submitted as proof of coverage:

- Certificate of Insurance ACORD Form 25 or other equivalent certificate of insurance form
- Additional Insured (General Liability) The combination of (ISO Forms) CG 20 10 and CG 20 37

All other additional insured endorsements must be submitted for approval by OC SAN, and OC SAN may reject alternatives that provide different or less coverage to OC SAN.
- Additional Insured (Automobile Liability) Submit endorsement provided by carrier for OC SAN approval.
- Waiver of Subrogation Submit workers' compensation waiver of subrogation endorsement provided by carrier for OC SAN approval.
- Cancellation Notice No endorsement is required. However, CONSULTANT is responsible for notifying OC SAN of any pending or actual insurance policy cancellation, as described in Article I. Cancellation and Policy Change Notice, below.

I. Cancellation and Policy Change Notice

The CONSULTANT is required to notify OC SAN in writing of any insurance cancellation notice it receives or other knowledge of pending or actual insurance policy cancellation within two (2) working days of receipt of such notice or acquisition of such knowledge. Additionally, the CONSULTANT is required to notify OC SAN in writing of any change in the terms of insurance, including reduction in coverage or increase in deductible/SIR, within two (2) working days of receipt of such notice or knowledge of same.

Said notices shall be mailed to OC SAN at:

ORANGE COUNTY SANITATION DISTRICT
18480 Bandilier Circle
Fountain Valley, CA 92708
Attention: Contracts, Purchasing & Materials Management Division

J. Primary Insurance

The general and automobile liability policies shall contain a Primary and “Non Contributory” clause. Any other insurance maintained by OC SAN shall be excess and not contributing with the insurance provided by CONSULTANT.

K. Separation of Insured

The general and automobile liability policies shall contain a “Separation of Insureds” clause.

L. Non-Limiting (if applicable)

Nothing in this document shall be construed as limiting in any way, nor shall it limit the indemnification provision contained in this Agreement, or the extent to which CONSULTANT may be held responsible for payment of damages to persons or property.

M. Deductibles and Self-Insured Retentions

Any deductible and/or self-insured retention must be declared to OC SAN on the certificate of insurance. All deductibles and/or self-insured retentions require approval by OC SAN. At the option of OC SAN, either: the insurer shall reduce or eliminate such deductible or self-insured retention as respects OC SAN; or the CONSULTANT shall provide a financial guarantee satisfactory to OC SAN guaranteeing payment of losses and related investigations, claim administration and defense expenses.

N. Defense Costs

The general and automobile liability policies shall have a provision that defense costs for all insureds and additional insureds are paid in addition to and do not deplete any policy limits.

O. Subconsultants

The CONSULTANT shall be responsible to establish insurance requirements for any Subconsultant hired by the CONSULTANT. The insurance shall be in amounts and types reasonably sufficient to deal with the risk of loss involving the Subconsultant’s operations and work.

P. Limits Are Minimums

If the CONSULTANT maintains higher limits than any minimums shown above, then OC SAN requires and shall be entitled to coverage for the higher limits maintained by CONSULTANT.

8. SCOPE CHANGES

In the event of a change in the Scope of Work or other terms in the Agreement, as requested by OC SAN, the parties hereto shall execute an Amendment to this Agreement setting forth with particularity all terms of the new Agreement, including, but not limited to, any additional CONSULTANT's fees. CONSULTANT hereby agrees to use any and all procedures, programs, and systems required by OC SAN to process and execute such Amendment(s), including, but not limited to, computer programs and systems.

9. PROJECT TEAM AND SUBCONSULTANTS

CONSULTANT shall provide to OC SAN, prior to execution of this Agreement, the names and full description of all Subconsultants and CONSULTANT's project team members anticipated to be used on this project by CONSULTANT. CONSULTANT shall include a description of the scope of work to be done by each Subconsultant and each CONSULTANT's project team member. CONSULTANT shall include the respective compensation amounts for CONSULTANT and each Subconsultant on a per task basis, broken down as indicated in Section 2 - COMPENSATION.

There shall be no substitution of the listed Subconsultants and CONSULTANT's project team members without prior written approval by OC SAN.

10. ENGINEERING REGISTRATION

The CONSULTANT's personnel are comprised of registered engineers and a staff of specialists and draftsmen in each department. The firm itself is not a registered engineer but represents and agrees that wherever in the performance of this Agreement requires the services of a registered engineer, such services hereunder will be performed under the direct supervision of registered engineers.

11. AUDIT PROVISIONS

- A. OC SAN retains the reasonable right to access, review, examine, and audit, any and all books, records, documents, and any other evidence of procedures and practices that OC SAN determines are necessary to discover and verify that the CONSULTANT is in compliance with all requirements under this Agreement. The CONSULTANT shall include OC SAN's right as described above, in any and all of their subcontracts, and shall ensure that these rights are binding upon all Subconsultants.
- B. OC SAN retains the right to examine CONSULTANT's books, records, documents and any other evidence of procedures and practices that

OC SAN determines are necessary to discover and verify all direct and indirect costs, of whatever nature, which are claimed to have been incurred, or anticipated to be incurred or to ensure CONSULTANT's compliance with all requirements under this Agreement during the term of this Agreement and for a period of three (3) years after its termination.

- C. CONSULTANT shall maintain complete and accurate records in accordance with generally accepted industry standard practices and OC SAN's policy. The CONSULTANT shall make available to OC SAN for review and audit, all project related accounting records and documents, and any other financial data within 15 days after receipt of notice from OC SAN. Upon OC SAN's request, the CONSULTANT shall submit exact duplicates of originals of all requested records to OC SAN. If an audit is performed, CONSULTANT shall ensure that a qualified employee of the CONSULTANT will be available to assist OC SAN's auditor in obtaining all project related accounting records and documents, and any other financial data.

12. LEGAL RELATIONSHIP BETWEEN PARTIES

The legal relationship between the parties hereto is that of an independent contractor and nothing herein shall be deemed to make CONSULTANT an employee of OC SAN.

13. NOTICES

All notices hereunder and communications regarding the interpretation of the terms of this Agreement, or changes thereto, shall be effected by delivery of said notices in person or by depositing said notices in the U.S. mail, registered or certified mail, return receipt requested, postage prepaid.

Notices shall be mailed to OC SAN at:

ORANGE COUNTY SANITATION DISTRICT
18480 Bandilier Circle
Fountain Valley, CA 92708
Attention: Yai Phongmekhin, Contracts Administrator
Copy: Omeed Pour, Project Manager

Notices shall be mailed to CONSULTANT at:

Dudek
687 S Coast Highway 101
Suite 110
Encinitas, CA 92024
Attention: Brandon Lacap, Project Manager

All communication regarding the Scope of Work, will be addressed to the Project Manager. Direction from other OC SAN's staff must be approved in writing by OC SAN's Project Manager prior to action from the CONSULTANT.

14. TERMINATION

OC SAN may terminate this Agreement at any time, without cause, upon giving thirty (30) days written notice to CONSULTANT. In the event of such termination, CONSULTANT shall be entitled to compensation for work performed on a prorated basis through and including the effective date of termination.

CONSULTANT shall be permitted to terminate this Agreement upon thirty (30) days written notice only if CONSULTANT is not compensated for billed amounts in accordance with the provisions of this Agreement, when the same are due.

Notice of termination shall be mailed to OC SAN and/or CONSULTANT in accordance with Section 13 - NOTICES.

15. DOCUMENTS AND STUDY MATERIALS

The documents and study materials for this project shall become the property of OC SAN upon the termination or completion of the work. CONSULTANT agrees to furnish to OC SAN copies of all memoranda, correspondence, computation and study materials in its files pertaining to the work described in this Agreement, which is requested in writing by OC SAN.

16. COMPLIANCE

A. Labor

CONSULTANT certifies by the execution of this Agreement that it pays employees not less than the minimum wage as defined by law, and that it does not discriminate in its employment with regard to race, color, religion, sex or national origin; that it is in compliance with all federal, state and local directives and executive orders regarding non-discrimination in employment; and that it agrees to demonstrate positively and aggressively the principle of equal opportunity in employment.

B. Air Pollution

CONSULTANT and its subconsultants and subcontractors shall comply with all applicable federal, state and local air pollution control laws and regulations.

C. Iran Contracting Act

CONSULTANT and its subconsultants and subcontractors shall comply with the Iran Contracting Act of 2010 (Public Contract Code sections 2200-2208).

D. California Air Resources Board Mobile Source Regulations

CONSULTANT and its subconsultants and subcontractors shall comply with the following California Air Resources Board Mobile Source Regulations:

- Advanced Clean Fleet (ACF): 13 CCR 2013-2013.4; 13 CCR 2015-2015.6
- Truck & Bus Regulation (T&B): 13 CCR 2025
- Clean Truck Check (CTC): 13 CCR 2195-2199.1
- Off-Road Diesel Amendments (ORD): 13 CCR 2449-2449.2

17. AGREEMENT EXECUTION AUTHORIZATION

Both OC SAN and CONSULTANT do covenant that each individual executing this document by and on behalf of each party is a person duly authorized to execute agreements for that party.

18. DISPUTE RESOLUTION

In the event of a dispute arising between the parties regarding performance or interpretation of this Agreement, the dispute shall be resolved by binding arbitration under the auspices of the Judicial Arbitration and Mediation Service (“JAMS”), or similar organization or entity conducting alternate dispute resolution services.

19. ATTORNEY’S FEES, COSTS AND NECESSARY DISBURSEMENTS

If any action at law or in equity or if any proceeding in the form of an Alternative Dispute Resolution (ADR) is necessary to enforce or interpret the terms of this Agreement, the prevailing party shall be entitled to reasonable attorney’s fees, costs and necessary disbursements in addition to any other relief to which it may be entitled.

20. PROGRESS REPORTS

Monthly progress reports shall be submitted for review by the tenth day of the following month and must include as a minimum: 1) current activities, 2) future activities, 3) potential items that are not included in the Scope of Work, 4) concerns and possible delays, 5) percentage of completion, and 6) budget status.

21. WARRANTY

CONSULTANT shall perform its services in accordance with generally accepted industry and professional standards. If, within the 12-month period following completion of its services, OC SAN informs CONSULTANT that any part of the services fails to meet those standards, CONSULTANT shall, within the time prescribed by OC SAN, take all such actions as are necessary to correct or complete the noted deficiency(ies).

22. INDEMNIFICATION

To the fullest extent permitted by law, CONSULTANT shall indemnify, defend (at CONSULTANT’s sole cost and expense and with legal counsel approved by OC SAN, which approval shall not be unreasonably withheld), protect and hold harmless OC SAN and all of OC SAN’s officers, directors, employees, consultants, and agents (collectively the “Indemnified Parties”), from and against any and all claims, damages, liabilities, causes of action, suits, arbitration awards, losses, judgments, fines, penalties, costs and expenses (including, without limitation, attorneys’ fees, disbursements and court costs, and all other professional, expert or CONSULTANT’s fees and costs and OC SAN’s

general and administrative expenses; individually, a "Claim"; collectively, "Claims") which may arise from or are in any manner related, directly or indirectly, to any work performed, or any operations, activities, or services provided by CONSULTANT in carrying out its obligations under this Agreement to the extent of the negligent, recklessness and/or willful misconduct of CONSULTANT, its principals, officers, agents, employees, CONSULTANT's suppliers, CONSULTANT, Subconsultants, subcontractors, and/or anyone employed directly or indirectly by any of them, regardless of any contributing negligence or strict liability of an Indemnified Party. Notwithstanding the foregoing, nothing herein shall be construed to require CONSULTANT to indemnify the Indemnified Parties from any Claim arising solely from:

- (A) the active negligence or willful misconduct of the Indemnified Parties; or
- (B) a natural disaster or other act of God, such as an earthquake; or
- (C) the independent action of a third party who is neither one of the Indemnified Parties nor the CONSULTANT, nor its principal, officer, agent, employee, nor CONSULTANT's supplier, CONSULTANT, Subconsultant, subcontractor, nor anyone employed directly or indirectly by any of them.

Exceptions (A) through (B) above shall not apply, and CONSULTANT shall, to the fullest extent permitted by law, indemnify the Indemnified Parties, from Claims arising from more than one cause if any such cause taken alone would otherwise result in the obligation to indemnify hereunder.

CONSULTANT's liability for indemnification hereunder is in addition to any liability CONSULTANT may have to OC SAN for a breach by CONSULTANT of any of the provisions of this Agreement. Under no circumstances shall the insurance requirements and limits set forth in this Agreement be construed to limit CONSULTANT's indemnification obligation or other liability hereunder. The terms of this Agreement are contractual and the result of negotiation between the parties hereto. Accordingly, any rule of construction of contracts (including, without limitation, California Civil Code Section 1654) that ambiguities are to be construed against the drafting party, shall not be employed in the interpretation of this Agreement.

23. DUTY TO DEFEND

The duty to defend hereunder is wholly independent of and separate from the duty to indemnify and such duty to defend shall exist regardless of any ultimate liability of CONSULTANT and shall be consistent with Civil Code Section 2782.8. Such defense obligation shall arise immediately upon presentation of a Claim by any person if, without regard to the merit of the Claim, such Claim could potentially result in an obligation to indemnify one or more Indemnified Parties, and upon written notice of such Claim being provided to CONSULTANT. Payment to CONSULTANT by any Indemnified Party or the payment or advance of defense costs by any Indemnified Party shall not be a condition precedent to enforcing such Indemnified Party's rights to indemnification hereunder. In the event a final judgment, arbitration, award, order, settlement, or other final resolution expressly determines that the claim did not arise out of, pertain to, or relate to the negligence, recklessness, or willful misconduct of the CONSULTANT, to any extent, then OC SAN will reimburse CONSULTANT for the reasonable costs of defending the Indemnified Parties against such claims.

CONSULTANT's indemnification obligation hereunder shall survive the expiration or earlier termination of this Agreement until such time as action against the Indemnified Parties for such matter indemnified hereunder is fully and finally barred by the applicable statute of limitations.

24. CONSULTANT PERFORMANCE

The CONSULTANT's performance shall be evaluated by OC SAN. A copy of the evaluation shall be sent to the CONSULTANT for comment. The evaluation, together with the comments, shall be retained by OC SAN and may be considered in future CONSULTANT selection processes.

25. COMPLIANCE WITH OC SAN POLICIES AND PROCEDURES

CONSULTANT shall comply with all OC SAN policies and procedures, including, but not limited to, the Contractor Safety Standards, as applicable, and Human Resources Policies, all as may be amended from time to time.

26. CLOSEOUT

When OC SAN determines that all work authorized under the Agreement is fully complete and that OC SAN requires no further work from CONSULTANT, or the Agreement is otherwise terminated or expires in accordance with the terms of the Agreement, OC SAN shall give the Consultant written notice that the Agreement will be closed out. CONSULTANT shall submit all outstanding billings, work submittals, deliverables, reports or similarly related documents as required under the Agreement within thirty (30) days of receipt of notice of Agreement closeout.

Upon receipt of CONSULTANT's submittals, OC SAN shall commence a closeout audit of the Agreement and will either:

- i. Give the CONSULTANT a final Agreement Acceptance: or
- ii. Advise the CONSULTANT in writing of any outstanding item or items which must be furnished, completed, or corrected at the CONSULTANT's cost.

CONSULTANT shall be required to provide adequate resources to fully support any administrative closeout efforts identified in this Agreement. Such support must be provided within the timeframe requested by OC SAN.

Notwithstanding the final Agreement Acceptance the CONSULTANT will not be relieved of its obligations hereunder, nor will the CONSULTANT be relieved of its obligations to complete any portions of the work, the non-completion of which were not disclosed to OC SAN (regardless of whether such nondisclosures were fraudulent, negligent, or otherwise); and the CONSULTANT shall remain obligated under all those provisions of the Agreement which expressly or by their nature extend beyond and survive final Agreement Acceptance.

Any failure by OC SAN to reject the work or to reject the CONSULTANT's request for final Agreement Acceptance as set forth above shall not be deemed to be acceptance of the work by OC SAN for any purpose nor imply acceptance of, or agreement with, the CONSULTANT's request for final Agreement Acceptance.

27. ENTIRE AGREEMENT

This Agreement constitutes the entire understanding and agreement between the Parties and supersedes all previous negotiations between them pertaining to the subject matter thereof.

IN WITNESS WHEREOF, this Agreement has been executed in the name of OC SAN and CONSULTANT by their respective duly authorized officers as of the day and year first written above.

DUDEK

By _____ Date _____

Printed Name & Title

ORANGE COUNTY SANITATION DISTRICT

By _____ Date _____
Ryan P. Gallagher
Board Chairman

By _____ Date _____
Kelly A. Lore
Clerk of the Board

By _____ Date _____
Kevin Work
Purchasing & Contracts Manager

- Attachments:
- Attachment "A" – Scope of Work
 - Attachment "B" – Labor Hour Matrix
 - Attachment "C" – Not Attached
 - Attachment "D" – Allowable Direct Costs
 - Attachment "E" – Fee Proposal
 - Attachment "F" – Not Used
 - Attachment "G" – Not Attached
 - Attachment "H" – Not Used
 - Attachment "I" – Cost Matrix and Summary
 - Attachment "J" – Not Attached
 - Attachment "K" – Minor Subconsultant Hourly Rate Schedule
 - Attachment "L" – Contractor Safety Standards
 - Attachment "M" – Not Attached
 - Attachment "N" – Not Attached
 - Attachment "O" – Human Resources Policies

YP

ATTACHMENT “A”

SCOPE OF WORK

ATTACHMENT "A"

SCOPE OF WORK

MacArthur Pump Station Rehabilitation
Project No. 7-63

TABLE OF CONTENTS

1.	PROJECT REQUIREMENTS	5
1.0	SUMMARY	5
1.0.1	Professional Design Engineering Services.....	5
1.0.2	Professional Licensing requirements.....	5
1.1	BACKGROUND	5
1.2	GENERAL PROJECT DESCRIPTION	6
1.3	PROJECT EXECUTION PHASES	6
1.4	DESCRIPTION OF PROJECT ELEMENTS	6
1.4.1	Project Element 1 – Wet Well Rehabilitation.....	6
1.4.2	Project Element 2 – Pump Room Rehabilitation.....	7
1.4.3	Project Element 3 – Electrical Room Improvements.....	7
1.4.4	Project Element 4 – Address Hazardous Area Classification.....	8
1.4.5	Project Element 5 – Wall Repairs	8
1.4.6	Temporary Facilities During Construction.....	8
1.4.7	Coordination with Other Projects	9
1.5	DESIGN CONSIDERATIONS	9
1.5.1	Technology and configuration choices.....	9
1.5.2	Design Decisions.....	9
1.5.3	Design Selection Criteria.....	9
1.5.4	Construction Cost Estimate.....	9
1.6	PROJECT SCHEDULE	9
1.6.1	General.....	9
2.	PHASE 2 – PRELIMINARY DESIGN	10
2.0	PRELIMINARY DESIGN EXECUTION	10
2.0.1	Major Decisions	10
2.1	PREDESIGN EVALUATION STUDIES (NOT USED)	11
2.2	PRELIMINARY DESIGN PRODUCTION	11
2.2.1	General.....	11
2.2.2	Design Memos	11
2.2.3	Preliminary Design Drawings.....	13
2.2.4	Preliminary Design Report (PDR) Production, Contents and Organization 13	
2.2.5	Preliminary Design Cost Estimate	14
2.3	PRELIMINARY DESIGN ACTIVITIES	14
2.3.1	Hazardous Area De-Classification Approach.....	14
2.3.2	Waterproofing Approach.....	14
2.3.3	DCS Server Installation Requirements and Approach.....	14
2.3.4	Equipment arrangement.....	15
2.3.5	Implementation Plan and Construction Sequencing	15
2.3.6	Easements, Property Boundaries and Work Area Limits	15
2.3.7	Topographic Survey	15
2.3.8	Traffic Control Services	15
2.3.9	Utility Investigation.....	16
2.3.10	Environmental Documentation	17
2.3.11	Permitting Assistance.....	18
2.3.12	Project Safety Review.....	18
2.3.13	Project Management.....	19

	2.3.14 Risk Management.....	20
	2.3.15 Quality Control	20
2.4	PDR WORKSHOPS AND MEETINGS	20
	2.4.1 General.....	20
	2.4.2 PDR Production Workshops	20
	2.4.3 Design memo Workshops	21
	2.4.4 PDR Review Workshops	21
	2.4.5 Maintainability Workshops.....	21
	2.4.6 Technical Progress Meetings	22
	2.4.7 Focused Meetings	22
	2.4.8 Coordination with Other Projects Meetings	23
	2.4.9 Stormwater Compliance Meeting.....	23
3.	PHASE 3 – DESIGN.....	23
3.0	BID DOCUMENTS	23
	3.0.1 General.....	23
	3.0.2 Engineering Design Guideline Updates	23
	3.0.3 General Requirements and Additional General Requirements	23
	3.0.4 Design Submittals.....	24
	3.0.5 Cable and Conduit Schedule	24
	3.0.6 Commissioning Plan Materials	24
	3.0.7 Equipment and Instrumentation Database (EID).....	25
	3.0.8 Real IO List.....	25
	3.0.9 Construction Submittal Items List.....	25
	3.0.10 Temporary Facilities During Construction.....	25
3.1	DESIGN SUPPORT DOCUMENTATION.....	26
	3.1.1 Design Submittal Support Documentation.....	26
	3.1.2 Construction Cost Estimate.....	27
	3.1.3 Construction Schedule.....	27
	3.1.4 Procurement Alternatives	27
3.2	DESIGN ACTIVITIES	27
	3.2.1 Easements, Property Boundaries and Work Area Limits	27
	3.2.2 Topographic Survey	27
	3.2.3 Utility Investigation.....	28
	3.2.4 Fire Protection Services.....	28
	3.2.5 Traffic Control Services	28
	3.2.6 Public Relations	28
	3.2.7 Environmental Documentation	28
	3.2.8 Permitting assistance	28
	3.2.9 Project Safety Review.....	28
	3.2.10 Project Management	29
	3.2.11 Risk Management.....	29
	3.2.12 Quality Control	29
3.3	DESIGN WORKSHOPS AND MEETINGS	29
	3.3.1 General.....	29
	3.3.2 Design Phase Workshops.....	29
	3.3.3 Post-DS2 Constructability Workshop	30
	3.3.4 Design Phase Meetings.....	31
	3.3.5 CONSULTANT Office Technical Meetings (COTMs)	32
	3.3.6 Coordination with Other Projects Meetings	32
	3.3.7 Commissioning Team Meetings.....	34

3.3.8	Project Safety	34
3.3.9	Construction Submittal Items List Meeting	34
3.3.10	Stormwater Compliance Meeting	35
3.4	BID PHASE SUPPORT SERVICES	35
3.4.1	Bid Phase Support Services	35
3.4.2	Bid Evaluation Assistance	35
3.4.3	Conformed Document Preparation	35
4.	PHASE 4 – CONSTRUCTION AND INSTALLATION SERVICES	35
5.	PHASE 5 – COMMISSIONING SERVICES	35
6.	PHASE 6 – CLOSE OUT	35
7.	GENERAL REQUIREMENTS	35
7.0	GENERAL	35
7.0.1	OC SAN Engineering Design Guidelines and Strategic Plan	35
7.0.2	Project Phases and Tasks.....	36
7.0.3	Construction Sequencing and Constraints	36
7.0.4	Working Hours	36
7.0.5	Standard Drawings and Typical Details	37
7.0.6	Software	37
7.0.7	Submittal Review using Bluebeam	37
7.0.8	Word Track Changes	37
7.0.9	GIS Submittals	37
8.	PROJECT-SPECIFIC DEVIATIONS FROM OC SAN DESIGN GUIDELINES	39
8.0	ENGINEERING DESIGN GUIDELINES CHAPTER 01, “DESIGN GUIDELINES – GENERAL REQUIREMENTS”	39
8.0.1	Engineering Design Guidelines Chapter 06, “Mechanical Design”	39
9.	STAFF ASSISTANCE	40
10.	EXHIBITS	40

1. PROJECT REQUIREMENTS

1.0 SUMMARY

1.0.1 PROFESSIONAL DESIGN ENGINEERING SERVICES

A. Provide professional design engineering services for the project described herein including the following:

1. Engineering studies
2. Preliminary Design Report
3. Permitting assistance
4. Preparation of bid documents

1.0.2 PROFESSIONAL LICENSING REQUIREMENTS

A. All plans and specifications shall be prepared by a professional engineer licensed in the State of California of the associated discipline.

1.1 BACKGROUND

The existing MacArthur Pump Station (Exhibit 19 – Project Reference Material) is an underground pump station that was built in 1965 and is located on an easement in the City of Newport Beach. The existing pump station is surrounded by commercial land use and is accessed from the west side of MacArthur Blvd, approximately 500 feet north of Von Karman Avenue (Figure 1 – Project Location Map). An existing 21-inch influent pipe conveys flow into the wet well. The existing 12-inch forcemain exiting the pump station was abandoned and replaced with a 10-inch dual forcemain by Project 7-68 (Exhibit 19 – Project Reference Material). In addition, as part of Project 7-68, the existing valve vault was removed and replaced.

The assets within the existing pump station are reaching the end of their useful life and require replacement or rehabilitation. A condition assessment of the pump station revealed exposed aggregate with $\frac{1}{2}$ "-1" of soft concrete, corroded steel, and corrosion stains in the wet well, and observed significant coating failures and corrosion on the pump supports, pump suction pipe sections, pipe supports, pump casings, and discharge pipes. See Exhibit 19 – Project Reference Material for an evaluation of the existing pump station. A structural evaluation of the pump station found that the overall pump station structure appeared to be in condition, however, moisture intrusion was observed, likely due to groundwater. See Exhibit 19 – Project Reference Material for a structural evaluation of the pump station.

For these reasons, OC SAN has decided to rehabilitate the pump station within the boundaries of the existing footprint, extending the life of the existing pump station without a full replacement for another 20 to 30 years.




Figure 1 – Project Location Map

1.2 GENERAL PROJECT DESCRIPTION

The project consists of rehabilitating the existing wet well concrete, replacing all existing internal equipment in the pump station and electrical rooms, addressing area classification, and repairing the pump room and electrical room walls.

1.3 PROJECT EXECUTION PHASES

All OC SAN projects are divided into six phases. CONSULTANT shall provide engineering services for all Project Elements listed in this Scope of Work for the following Phases:

- Phase 1 – Project Development (Not in this Scope of Work)
- Phase 2 – Preliminary Design
- Phase 3 – Design
- Phase 4 – Construction (Not in this Scope of Work)
- Phase 5 – Commissioning (Not in this Scope of Work)
- Phase 6 – Close Out (Not in this Scope of Work)

1.4 DESCRIPTION OF PROJECT ELEMENTS

Detailed descriptions of the Project Elements are presented below.

1.4.1 PROJECT ELEMENT 1 – WET WELL REHABILITATION

- A. The existing soft concrete on the surface of the wet well will be rehabilitated and the internal surface will be lined.

B. Assumptions for Level of Effort

1. For the purpose of estimating the predesign and design phase levels of effort, the CONSULTANT shall make the following assumptions regarding this project element:
 - a. Suction bell elbows will be replaced.
 - b. The existing bubbler system will be demolished and removed in this project. One existing ultrasonic transmitter and one radar level transmitter are to be protected in place.

1.4.2 PROJECT ELEMENT 2 – PUMP ROOM REHABILITATION

A. The pump room rehabilitation element consists of the replacement of all internal mechanical equipment. Flowrates (MGD) are shown in the table below:

Reported Capacity	2017 PDWF	2017 PWWF	2040 PDWF	2040 PWWF
3.6	1.7	2.3	2.0	2.5

B. The pump room will house the following components and provide the necessary access required for operations and maintenance:

1. Replace existing pumps with (2) dry submersible main sewage pumps (One duty pump and one standby pump – the same size) with pump motors controlled by variable frequency drives (VFDs) that are equipped with constant speed bypass mode of operation.
2. Replace submersible, non-clog sump pump
3. Replace suction, header, discharge pipe, wall spool, wall pipe penetration, pipe supports, and associated valves
4. New flow meter

C. Assumptions for Level of Effort

1. For the purpose of estimating the predesign and design phase levels of effort, the CONSULTANT shall make the following assumptions regarding this project element:
 - a. All new equipment will be replaced within the same footprint.

1.4.3 PROJECT ELEMENT 3 – ELECTRICAL ROOM IMPROVEMENTS

A. Replace all existing electrical, mechanical and control equipment including but not limited to the following:

1. (2) Motor control centers (MCCs)
2. (2) Variable frequency drives (VFDs - included with Constant Speed Bypass)
3. Metering Switchboard
4. Utility Switchboard
5. Transformer
6. Panelboards
7. Distributed control system (DCS) Controller
8. Remote Input/Output (RIO) Cabinet (included with DCS Controller)
9. Uninterruptable power supply (UPS)
10. Replace existing selector switch panel and level instruments

11. DCS server cabinet with front and rear floor access
12. Redundant DCS servers and supporting communications equipment
13. Operator workstation cabinet
14. Go/No-Go Panel, Lighting and Signage (New)

B. Assumptions for Level of Effort

1. For the purpose of estimating the predesign and design phase levels of effort, the CONSULTANT shall make the following assumptions regarding this project element:

- a. The Level Measurement system is to be replaced with a combination Ultrasonic and Radar Level Monitoring System per Project No. FE23-03 and to be completed prior to this project. The transmitter panel of the combination ultrasonic and radar level measurement system may need to be re-used and relocated to accommodate for the installation of the new electrical and mechanical equipment in the electrical room. The existing bubbler panel and air compressors will be demolished and removed as part of this project.
- b. All new equipment will be installed within the existing footprint of the electrical room.

1.4.4 PROJECT ELEMENT 4 – ADDRESS HAZARDOUS AREA CLASSIFICATION

A. The existing electrical room does not meet the current fire code and is classified as Class 1 Division 2. There is one existing aboveground supply fan, (1) 14” diameter supply duct in the pump room, and (1) 8” diameter exhaust duct in the electrical room. The existing ventilation system will be replaced with (1) duty and (1) standby fan that meet CCR Title 8 regulations, NFPA 820 and OC SAN design guidelines to declassify the electrical room.

1.4.5 PROJECT ELEMENT 5 – WALL REPAIRS

A. The dry well and electrical room wall cracks will be sealed and repaired to prevent corrosion of the wall reinforcing.

1.4.6 TEMPORARY FACILITIES DURING CONSTRUCTION

A. In certain cases, construction sequencing constraints may require the Contractor to construct a temporary facility to be used during a certain portion of the construction period. CONSULTANT shall identify in what instances such facilities are required or reasonably warranted and present those instances with implementation plans and construction sequencing constraints to OC SAN for consideration. When such facilities are found to be either required or reasonably warranted, CONSULTANT shall provide sufficiently detailed drawings and specifications to be included in the Bid Documents that bidders understand what is required to provide and potentially operate the temporary facilities and that the reliability and performance of the facilities will meet OC SAN’s needs and reasonably mitigate construction risks. Examples of potential facilities include:

1. A bypass pumping system will be required for temporary handling of flows during construction. Influent flows will be captured at the upstream manhole (SUN0155-0285) and fed to the downstream dual 10” forcemains in the existing valve vault. Manhole SUN0155-0285 is located in the sidewalk within OC SAN’s easement. The temporary bypass pumping system must comply with OC SAN’s goal of zero sewage spills.
2. Temporary MCC or 480V panelboard to install new electrical equipment
3. Temporary standby power to accommodate the transfer of electrical loads from existing electrical equipment to new electrical equipment and the phasing of the electrical system from the existing standby power electrical distribution equipment and synchronizing controls to the new synchronizing switchgear.

1.4.7 COORDINATION WITH OTHER PROJECTS

A. The following projects may impact or require coordination with this project. The CONSULTANT shall coordinate with each project and incorporate work restrictions and requirements in the design documents.

1. City of Newport Beach Public Works Department, MacArthur Blvd Paving Improvements 2026-2027. The City of Newport Beach will be performing pavement rehabilitation on MacArthur Blvd from Jamboree Rd to Campus Dr tentatively January 2026.

1.5 DESIGN CONSIDERATIONS

The following design considerations shall be carried out from Preliminary Design through Final Design.

1.5.1 TECHNOLOGY AND CONFIGURATION CHOICES

The project elements in this facility shall be achieved using proven technologies. Alternative means of accomplishing the project elements must be reviewed and accepted by OC SAN prior to detailed evaluation. All alternative technologies proposed should be currently operating in other wastewater treatment facilities of similar capacity.

1.5.2 DESIGN DECISIONS

Design decisions shall be agreed upon by OC SAN prior to any work being performed by the CONSULTANT in preliminary and detailed design. All design decisions shall be documented.

1.5.3 DESIGN SELECTION CRITERIA

- A. Design selection shall consider construction, lifecycle, operation, and maintenance costs as well as process benefits and overall quality. When design recommendations are presented to OC SAN, the design selection criteria shall be clearly identified with the recommendation.
- B. The life cycle cost analysis for the options proposed shall include costs for engineering, construction, start-up, and operational and maintenance, and future rehabilitation and replacement. Life cycle cost analysis is described in Section 01.2.19 of the Engineering Design Guidelines. See **Exhibit 17 - OC SAN Engineering Design Guidelines and Standards – Available** online at [Document Central | Orange County Sanitation District \(ocsan.gov\)](https://documentcentral.ocsan.gov)
- C. The construction cost estimate shall be as described in the **Engineering Design Guidelines, Chapter 15 Construction Cost Estimates**.

1.5.4 CONSTRUCTION COST ESTIMATE

- A. The construction cost estimate shall be as described in the **Engineering Design Guidelines, Chapter 15 Construction Cost Estimates**.

1.6 PROJECT SCHEDULE

1.6.1 GENERAL

- A. The table below lists the time frames associated with each major project deliverable and with OC SAN's review and approval of those deliverables. CONSULTANT shall comply with the deadlines indicated in that table.
- B. OC SAN's Project Manager will issue a Preliminary Design NTP. OC SAN's Project Manager will also issue a Final Design NTP upon OC SAN's acceptance of the final Preliminary Design Report.
- C. The time frames specified below are used to estimate the actual milestone dates based on the assumed NTP date, as shown in **Exhibit 8 - Project Schedule Calculation**.
- D. OC SAN will consider an alternative CONSULTANT-proposed schedule provided it is consistent with OC SAN resources and schedule constraints and adds value to OC SAN.

PROJECT MILESTONE AND DEADLINES	
MILESTONE	DEADLINE
Kickoff Meeting	The kickoff meeting will be scheduled to coincide with the Preliminary Design NTP.
Preliminary Design NTP	
Submit draft Preliminary Design Report (PDR)	170 workdays from the Preliminary Design NTP. CONSULTANT shall establish a schedule with the OC SAN PM for separately submitting working drafts of each Design Memo for OC SAN review prior to completing the draft PDR. This schedule shall factor in the logical sequence for completing the memos as well as both CONSULTANT and OC SAN resources.
OC SAN Review of draft PDR	20 workdays from receipt of Draft PDR
Submit final Preliminary Design Report	40 workdays from receipt of OC SAN comments on Draft PDR.
Final Design NTP	CONSULTANT's schedule shall allow 15 working days from submittal of the final PDR to receipt of the Design Phase NTP.
Submit Design Submittal 1 (DS1)	80 workdays from Design Phase NTP.
OC SAN Review of DS1	15 workdays from receipt of DS1
Submit Design Submittal 2 (DS2)	80 workdays from receipt of OC SAN comments on DS1.
OC SAN Review of DS2	20 workdays from receipt of DS2
Submit Design Submittal 3 (DS3)	80 workdays from receipt of OC SAN comments on DS2.
OC SAN Review of DS3	20 workdays from receipt of DS3
Submit Final Design Submittal (FDS)	40 workdays from receipt of OC SAN comments on DS3. CONSULTANT shall stop work upon submission of DS3, except as required to participate in OC SAN meetings, until receipt of OC SAN comments on DS3.
OC SAN Review of FDS	15 workdays from receipt of FDS
Final Technical Specifications and Plans	25 workdays from receipt of OC SAN comments on FDS.

2. PHASE 2 – PRELIMINARY DESIGN

The preliminary design phase will define the project. The final deliverable of this phase will be a Preliminary Design Report (PDR) with the basis of design for all elements of the project.

2.0 PRELIMINARY DESIGN EXECUTION

2.0.1 MAJOR DECISIONS

A. The CONSULTANT shall plan the resolution of major decisions through the following process:

1. Identify major decisions early and the timing required to prevent impacts to the project schedule.
2. Identify the decision-making method that will be used to gain OC SAN concurrence and provide appropriate opportunities for OC SAN provide input.

3. Identify and schedule at the start of the project the workshops, technical design meetings and focused meetings where major decisions will be made and include a list of attendees required.

B. These decisions should be tracked on the Decision Log and flagged as a major decision. The Decision Log shall include a column for cost impact.

2.1 PREDESIGN EVALUTION STUDIES (NOT USED)

2.2 PRELIMINARY DESIGN PRODUCTION

2.2.1 GENERAL

A. Preliminary Design Report (PDR) production involves the preparation of design memos, drawings, calculations, and other supporting material resulting in the PDR.

2.2.2 DESIGN MEMOS

A. The CONSULTANT shall produce Design Memos as indicated with a check box below in accordance with **Exhibit 1 - Preliminary Design Report Requirements**. The CONSULTANT shall discuss the combining of design memos with OC SAN and develop a design memo submittal list.

Process Design Configuration

- Design Configuration
- Redundancy
- Monitoring and Sampling
- Process Flow Diagrams
- Operating Philosophies
- Site and Facility Layouts
- Preliminary Load Criticality Ranking Table

Hydraulic Analysis

- Static Analysis
- Dynamic Analysis
 - Dry Weather Calibration
 - Wet Weather Calibration
 - Design Storm Choice Sensitivity Analysis
- Hydraulic Profile

Demolition

- Describe Demolition Requirements
- Demolition List
- Demolition Plans
- Demo EID

Rehabilitation Requirements

Geotechnical Data Report

- Review of Existing Data - Preliminary Geotechnical Report
- Geotechnical Data Report and Recommendations

Civil Design Parameters

- General Civil
- Pavement Requirements
- Drainage Requirements
- Corrosion Protection Requirements

Utility Requirements

Structural Design Parameters

Architectural Design Parameters

- Process Mechanical Design Parameters**
- Building Mechanical Design Parameters**
- Fire Protection**
 - Fire Protection Requirements
 - Fire Water Flow Analysis
 - Fire Protection Requirements for Existing Facilities
- Electrical**
 - Codes/standards. Brief description of electrical system. Electrical drawings.
 - Identify Electrical System Impacts
 - Report – Data Collection and Verification
 - Preliminary Load List
 - Preliminary Standby Power Requirements
 - ETAP – Preliminary Short Circuit Analysis and Load Flow/Voltage Drop Studies
 - ETAP – Provide Data. OC SAN will perform ETAP studies.
 - Preliminary Analysis for cable pull calcs, ductbank cable derating, cable tray fill calcs.
 - Hazardous Area Classification Requirements
- Instrumentation and Control**
 - Instrumentation and Control System
 - DCS Server Requirements
 - Preliminary Real IO List
 - PLC and RIO Panel Location Map
 - CCTV Coverage Map
- Landscaping**
 - Landscaping Requirements
 - Develop up to three alternative concepts for review and acceptance
- Plant Utility Investigation Findings**
- Vibration Analysis**
- Collections Basis of Design**
 - Codes and Standards
 - Pipeline Basis of Design
 - Manhole Basis of Design
- Collections Rehabilitation Alternatives**
 - Wet Well Rehabilitation
 - Manhole Rehabilitation
- Collections Pipeline Design**
 - Assume 3 viable alignment options
 - Design Memo Items 1-12
 - Open-cut vs. Trenchless Technologies
 - Trenchless Technologies at Major Closings
- Collections Utility Investigation Findings**
- Collections Conceptual Traffic Control**
 - AHJ and Traffic Control Identification
 - Basis for Traffic Control Strategy
 - Traffic Analysis
 - Traffic Control Plans
- Design Safety Requirements**
 - Design Safety Requirements
 - Identify all potential project specific safety issues
 - Identify all potential Cal OSHA and OC SAN safety issues
 - Identify construction safety hazards

Project Safety Checklist (Exhibit 11) and Full Project Safety Review Plan (Exhibit 12) to verify safety elements

HAZOP

Public Impacts

Environmental and Regulatory Requirements

CEQA Part of Programmatic EIR

Determine project environmental and regulatory requirements

Matrix of CEQA and Permit Requirements

Mitigation, Monitoring and Reporting List

Permit Requirements

List of Permits Required

Oil Well Abandonment

Stormwater Requirements

Hazardous Material Survey, Mitigation and Control

Maintainability

Define Maintainability Requirements

Maintainability Requirements Plan Drawings

Define Maintainability Rules

Define Maintainability Information for Project Specific Equipment

Facility Operation and Maintenance

Facility O&M Requirements

Operating Philosophies

Preliminary Assessment of O&M Staffing Requirements

Implementation Plan

Identification of Adjacent Projects

Preliminary Commissioning Checklist

Preliminary Construction Sequencing Plan

Review of Constructability Issues

Temporary Handling of Flow

Construction Odor Monitoring and Mitigation

Preliminary Technical Specification List

2.2.3 PRELIMINARY DESIGN DRAWINGS

A. The CONSULTANT shall produce the following Preliminary Design Report drawings in accordance with **Exhibit 1 - Preliminary Design Report Requirements**.

General

Demolition

Civil

Landscape

Structural

Architectural

Mechanical

Electrical

Instrumentation and Control

2.2.4 PRELIMINARY DESIGN REPORT (PDR) PRODUCTION, CONTENTS AND ORGANIZATION

A. Preliminary Design Report (PDR) Production involves the preparation of design memos, drawings, calculations, and other supporting material resulting in the PDR.

B. The CONSULTANT shall combine the materials described below into a draft PDR. The PDR shall be structured as outlined below, with the contents corresponding to the tasks listed in this Scope of Work.

Volume 1 – Preliminary Design Report Technical Memos

Executive Summary

Design Memos

Design Memo 1, 2, 3, etc.

List of Proposed Specification Sections

Volume 2 – Drawings (see Preliminary Design Drawings list below)

Volume 3 – Submittal Documentation

Calculations

Equipment Data & Catalog Cuts

Decision Log

Meeting Minutes

Exhibit 11 - Project Safety Checklist

Exhibit 12 – Full Project Safety Review Plan

C. The Executive Summary shall summarize the conclusions of the Memos included in the report and specifically include a summary construction schedule and construction cost estimate.

D. The draft PDR and final PDR shall be submitted in searchable PDF format legible on-screen and as a hard copy. The number of hard copies is indicated in **Exhibit 9 - Deliverables Quantities**. The labeling and organization of the PDF submittal shall be in accordance with **Exhibit 14 - Bluebeam Designer Training for Submission**.

E. Each evaluation memo and design memo shall be a separate file.

F. The OC SAN Project Manager may request that the CONSULTANT submit an electronic proof set of the Draft PDR and Final PDR prior to hard copy production in order to initially confirm that the submittal is ready for printing.

2.2.5 PRELIMINARY DESIGN COST ESTIMATE

A. The CONSULTANT shall provide a cost estimate for the associated PDR submittal per **Engineering Design Guidelines, Chapter 15 Construction Cost Estimates**.

2.3 PRELIMINARY DESIGN ACTIVITIES

The following services shall be provided by the CONSULTANT or an appropriately qualified Subconsultant. In any case, the CONSULTANT shall be responsible for managing all subconsultants, including reviewing their work products prior to submission to OC SAN.

2.3.1 HAZARDOUS AREA DE-CLASSIFICATION APPROACH

A. The CONSULTANT shall evaluate the existing ventilation to the pump and electrical rooms and determine the ventilation needed to declassify the electrical room per NFPA 820. Include recommendations in the Electrical Design Memo.

2.3.2 WATERPROOFING APPROACH

A. Determine a waterproofing system for the pump room based on the structure design life, constructability, and cost benefit. Include recommendations in the Structural Design Memo.

2.3.3 DCS SERVER INSTALLATION REQUIREMENTS AND APPROACH

A. The CONSULTANT shall review the environmental and electrical requirements for the DCS servers and determine an installation method suitable for the location. The appropriate enclosure will need to have front and rear access from the floor. Clearances on the backside of the DCS server do not need to meet the OC SAN Engineering Design Guidelines Electrical Design Criteria minimum clearance requirement so long as operations staff are able to access the rear of the DCS server. Some server racks can be pulled out and

rotated, allowing access to the back, which is acceptable for the new DCS server design. The servers will have redundant power supplies which shall be fed from separately derived sources, with one source being UPS. Power quality will need to be evaluated, and conditioning provided as needed. The appropriate enclosure will have at least 25% of spare rack space for future equipment and capable of supporting those additional loading requirements.

2.3.4 EQUIPMENT ARRANGEMENT

A. CONSULTANT shall evaluate the equipment arrangement at the pump station. This includes ensuring accessibility for operating and maintaining equipment and ensure adequate working spaces.

2.3.5 IMPLEMENTATION PLAN AND CONSTRUCTION SEQUENCING

A. CONSULTANT shall prepare an implementation plan with construction sequencing. This includes identifying temporary facilities that will be required, and the means to operate them, during construction.

2.3.6 EASEMENTS, PROPERTY BOUNDARIES AND WORK AREA LIMITS

A. The CONSULTANT shall identify easement and property boundary requirements based on available record drawings and the survey/mapping information from Project 7-68 as well as the City of Newport Beach MacArthur Blvd Final Street Improvement plans provided to the CONSULTANT. Unless otherwise directed, the CONSULTANT shall identify, and show all property boundaries, and all existing and proposed easements, within and/or adjacent to the project boundaries.

B. CONSULTANT shall show and explicitly identify the limits of work for all portions of the project, including any restrictions to the work allowed in any area, e.g., whether the area can be used for parking or laydown.

2.3.7 TOPOGRAPHIC SURVEY

A. OC SAN will provide the survey information from Project 7-68 as well as the City of Newport Beach MacArthur Blvd Final Street Improvement plans to the CONSULTANT for use on the project.

B. The basis of bearings and benchmarks shall be indicated on the drawings. Control shall reference the Coordinate System and datum per OC SAN CAD STANDARDS MANUAL (CAD Manual), latest edition. CONSULTANT's project schedule shall account for the above.

C. Control Surveys for Collection Systems

1. Base Map: The base map index contours shall be spaced at five feet (5') vertically and the immediate contours shall be spaced at one-foot (1') contour intervals. The mapping shall include digital topographic mapping. The digital format shall be compatible with OC SAN Graphic Information System (GIS). All surface features, including those hidden from aerial view shall be incorporated into the digital mapping.

2. Plan and Profile Sheets: CONSULTANT shall prepare plan and profile sheets based upon the aerial mapping. The scale for plan and profile sheets shall be one inch equals forty feet (1" = 40') horizontal and one inch equals four feet (1" = 4') vertical. An aerial photographic (photo strip) with the alignment shall be included. The plan view shall be separate from the photo strip. Intersections shall be adequately detailed at a scale of one inch equals ten feet (1" = 10') or one inch equals twenty feet (1" = 20'). Manholes and other details shall be drawn at a scale that is adequate to provide clarity and sufficient detail for construction. The pump station construction drawings shall be drafted at scales of 1/8" = 1' to 1" = 20', as adequate, to allow for sufficient detail to be shown. The basis of bearings and benchmarks shall be indicated on the drawings.

2.3.8 TRAFFIC CONTROL SERVICES

A. CONSULTANT shall secure the services of a Subconsultant to determine the traffic control requirements and assist corresponding subconsultants in obtaining approval from the City of Newport Beach.

2.3.9 UTILITY INVESTIGATION

A. To better manage the risks associated with construction excavation, CONSULTANT shall perform a thorough search of all utilities impacted by the work for all applicable Project Elements of this Scope of Work, regardless of size and all other facilities above or below ground. Utilities include all utility company-owned and public agency-owned piping, duct banks, and other interferences. The search shall include utilities within the public right-of-way, and those located on private property and OC SAN property impacted by the proposed project. The search shall include the records and plans of OC SAN and all respective public and private companies and utilities.

B. Review of OC SAN Records

1. OC SAN's "As-built/Record" plans may be incomplete or inaccurate with respect to the routing of individual utilities, pipelines, etc. in the vicinity of the project. CONSULTANT shall check OC SAN records against those of the other agencies, companies and utilities. These may include, but not be limited to, oil, gas, fuel, water, and sewer pipelines; traffic control facilities, telephone and electrical conduit and duct banks, storm drains, manholes, and other structures.

C. Review of Outside Agency Records

1. CONSULTANT shall contact, in writing, all jurisdictional agencies and utility owners to inform them of OC SAN's project. CONSULTANT shall request plans showing all the agency's or utility's facilities, pipelines, etc. in the project area. CONSULTANT shall also request plans and schedules for all proposed construction in the project areas. CONSULTANT shall develop a schedule to minimize project conflicts and/or coordinate OC SAN projects with local agencies.

2. CONSULTANT shall personally visit each agency/company and search through all available plans, files, and documents. CONSULTANT shall meet with applicable field staff from each agency to confirm the completeness of their research. Abandoned utilities shall also be considered.

3. CONSULTANT shall document the contacts and information requested and received, including that from Underground Service Alert (USA). OC SAN shall be copied on all correspondence between CONSULTANT and public and private agencies, and utility companies. CONSULTANT shall submit a copy of all documentation to OC SAN with an itemized submittal letter. CONSULTANT's Project Manager shall sign the transmittal cover letter, and the cover letter shall confirm that CONSULTANT has sent a representative to each agency/company/utility, performed on-site inspections for each utility, and has listed the utilities.

4. CONSULTANT shall contact USA and request a Substructure listing for the project area.

D. On-Site Inspection

1. An on-site inspection shall be conducted in the project area. During the on-site inspection, a senior-level CONSULTANT representative shall walk the site accompanied by OC SAN's Project Engineer and Supervising Inspector. The CONSULTANT representative shall be experienced in the location and identification of utilities in the field. During the on-site inspection the CONSULTANT shall document all visible features that indicate utilities within the project area and compare them with the available utility plans.

E. Utilities for Adjacent Properties

1. CONSULTANT shall investigate all utilities serving properties adjacent to the work, and submit a spreadsheet at the end of the utility research accounting for all anticipated utilities for OC SAN review, with the following information:

- a. List all utilities anticipated on each adjacent property.
- b. Indicate whether or not each such utility was found on as-built drawings of any agency, with an identification of the agencies identifying such utility.
- c. Indicate whether or not the utility was field located by utility through USA process, and, if so, by which agency.

F. Subsurface Utility Investigations

1. Investigation of existing utilities shall be in accordance with the respective ASCE guidelines, except as amended by this Scope of Work. A brief description of the ASCE guidelines defines the Quality Level of detail for researching subsurface utilities as follows:

- a. **Quality Level D:** Information derived from existing records or oral recollections.
- b. **Quality Level C:** Information obtained by surveying and plotting visible above-ground utility features and by using professional judgment in correlating this information to Quality Level D information.
- c. **Quality Level B:** Information obtained through the application of appropriate surface geophysical methods to determine the existence and approximate position of subsurface utilities. Quality Level B data shall be reproducible by surface geophysics, such as ground penetrating radar, at any point of their depiction. This information is surveyed to applicable tolerances and reduced onto plan documents.
- d. **Quality Level A:** Precise horizontal and vertical location of utilities obtained by the actual exposure (or verification of previously exposed subsurface and surveyed utilities) and subsequent measurement of subsurface utilities, usually at a specific point. Minimally intrusive excavation equipment is typically used to minimize the potential for utility damage. A precise horizontal and vertical location, as well as other utility attributes, is shown on the plan documents. Accuracy is typically set to 15-mm vertical and to applicable horizontal survey and mapping accuracy.

2. Refer to CI/ASCE 38-22, Standard Guidelines for Collection and Depiction of Existing Subsurface Utility Data for details.

3. CONSULTANT shall determine all utilities impacted by the work for all applicable Project Elements of this Scope of Work. Utilities include utility company-owned, and public agency-owned piping, duct banks, and other interferences. All utilities encountered during the preliminary design shall be shown on the plans.

4. Subsurface investigation for all utilities in and around the work area shall be performed to Quality Level D and Quality Level C. All utilities shall be plotted both in plan and profile on a scaled drawing that can later be incorporated into scaled (1" = 40') plan drawings.

2.3.10 ENVIRONMENTAL DOCUMENTATION

A. CONSULTANT services related to Environmental Documentation may span across Phase 2 – Preliminary Design and Phase 3 - Design. When such services are required, they shall be based on the requirements of Section III – Project Schedule and based on the following requirements. The CONSULTANT shall allocate the budgeted hours between the Environmental Documentation services in Phase 2 and Phase 3 based on when these services will be required.

B. CEQA Documentation Support

1. OC SAN expects that a Notice of Exemption (NOE) will be required for this project. OC SAN will separately arrange for preparation of required NOE.

2.3.11 PERMITTING ASSISTANCE

- A. CONSULTANT services related to Permitting Assistance may span across Phase 2 – Preliminary Design and Phase 3 - Design. When such services are required, they will be based on the requirements of Section III – Project Schedule and the schedule constraints associated with each particular permit. The CONSULTANT shall allocate the budgeted hours between the Environmental Documentation services in Phase 2 and Phase 3 based on when these services will be required.
- B. For all applicable Project Elements of this Scope of Work, CONSULTANT shall provide Bid Documents that ensure that the facility features and the facility performance, and construction procedures comply with all conditions of existing permits and permits required to construct this project. Construction drawings, specifications and supplemental drawings shall be prepared, as necessary, in the format required to obtain all permits.
- C. CONSULTANT shall assist OC SAN in obtaining permits. This assistance shall include completing application forms provided by OC SAN, preparing supporting documentation for the permit applications as required by the issuing agency, furnishing the required number of copies of all construction drawings and exhibits, and attending meetings with permitting agencies at the request of OC SAN.
- D. With the exception of construction contractor-furnished permits, OC SAN staff will execute all applications. All permit fees will be paid directly by the OC SAN and will not be part of CONSULTANT's fee.
- E. CONSULTANT shall submit all supporting documentation in a timely fashion for all permits required for this project as described below.
- F. City / County Encroachment Permits
1. City of Newport Beach
 - a. The CONSULTANT shall assume 2 meetings at 2 hours each.
- G. Stormwater Permitting
1. CONSULTANT shall determine and specify the preliminary Risk Level and Project Type using the California State Water Resources Control Board's Storm Water Multiple Application and Report Tracking System (SMARTS) based on the R-Factor obtained from US EPA's online Rainfall Erosivity Factor Calculator for Small Construction Sites.
 2. CONSULTANT shall prepare the specification for stormwater using OC SAN's respective master specification as a starting point. CONSULTANT shall not begin work on editing the specification until OC SAN has approved the CONSULTANT's preliminary Risk Level and Project Type.
 3. It is OC SAN's intent to design linear underground/overhead projects (LUP) to LUP Type 2 requirements, whenever possible, which is often the most economical approach. CONSULTANT shall coordinate with the OC SAN Project Manager and OC SAN Environmental Compliance Division and edit Stormwater Pollution Prevention Plant specifications accordingly.

2.3.12 PROJECT SAFETY REVIEW

- A. CONSULTANT shall prepare Exhibit 11 Project Safety Check List and Exhibit 12 – Full Project Safety Review Plan for review with OC SAN Risk Management during the Preliminary Safety Review Plan Workshop. The workshop shall be held at OC SAN offices and no more than 4 hours. (held 4 weeks prior to draft PDR).
- B. Moderator
1. CONSULTANT shall provide a suitably qualified moderator to conduct the Workshops to review project safety topics contained in Exhibit 11 - Project Safety Check List and

Exhibit 12 - Full Project Safety Review Plan. The moderator shall have the following attributes:

- a. Sufficiently technically knowledgeable to understand the nature of the safety risks involved, but the moderator need not be a subject matter expert.
- b. Not extensively involved in the project to date, so that the moderator has no personal stake in the issues. CONSULTANT's Project Manager and Project Engineers for this project are not considered suitable.
- c. Employed by CONSULTANT, a Subconsultant, or a specific individual.

2.3.13 PROJECT MANAGEMENT

A. CONSULTANT shall be responsible for managing CONSULTANT's project execution, schedule, budget, subconsultants, and coordination with other projects. The CONSULTANT shall perform the project management requirements in accordance with **Exhibit 3 - Project Management Requirements** with the project specific options identified below.

B. Progress Reporting

- Earned Value Curve and Budget Status Graph
- Milestone-Based Tracking

C. Project Management Plan (PMP):

- Not required
- Required
 - PMP approval prior to beginning technical work on the project.

D. Project Logs

- Major Decision Log
- Project Decision Log
- Action Item Log
- Decision Issues Log
- Meeting Log
- Risk Register

E. Breakdown Structure (WBS)

1. The WBS shall serve as the unified framework for organizing and reporting project work. It will be jointly developed by OC SAN and the CONSULTANT and used for invoicing, monthly progress reporting, scheduling, and earned value management.
2. By establishing this structure collaboratively, OC SAN and the CONSULTANT ensure that all reporting and tracking activities are consistent, comparable, and based on a shared understanding of the project work.
3. The WBS must accommodate the cost codes as shown below

F. Progress Report

- Not required
- Required

G. Project Invoices

1. Estimating earned value, tasks shall be further broken down to subtasks of no more than \$100,000.
2. Costs for invoicing shall be grouped into the following work packages:

Work Package	Description	Tasks
3146	Preliminary Design	All Phase 2 tasks, except those listed above.
3250	CONSULTANT Services During Design	Tasks 3.1 through 3.4, and 3.6 through 3.12
3254	Bid Support Services	Task 3.5

2.3.14 RISK MANAGEMENT

A. CONSULTANT shall provide risk management in accordance with Exhibit 4 – Risk Management Requirements.

2.3.15 QUALITY CONTROL

A. The CONSULTANT shall provide quality control requirements in accordance with **Exhibit 6 - Quality Control Requirements**.

2.4 PDR WORKSHOPS AND MEETINGS

2.4.1 GENERAL

A. Workshop and meeting planning, requirements, agendas, and meeting minutes shall be in accordance with **Exhibit 5 - Workshop and Meeting Requirements**.

2.4.2 PDR PRODUCTION WORKSHOPS

A. Predesign Kickoff Workshop

1. A two-hour project kick-off meeting shall be held with OC SAN staff to introduce principal members of OC SAN and CONSULTANT's teams. The discussion topics shall include OC SAN responsibilities, CONSULTANT's responsibilities, invoice procedures, personnel badges, parking, site access, CONSULTANT's Scope of Work, detailed project schedule with milestones, Work Breakdown Structure requirements, and project safety requirements.

B. PDR Production Workshops shall be held during Preliminary Design to review project progress during PDR Production. The subjects to be covered in each workshop are discussed below. Each workshop shall be **2** hours in length.

C. PDR Production Workshops shall be held during Preliminary Design to review the topics listed below. The list below also indicates the number of workshops to be held to cover the specific topic. Unless otherwise noted, each workshop shall be **2** hours in length.

PDR PRODUCTION WORKSHOPS	
TOPIC	NUMBER OF WORKSHOPS
PDR Production Workshops:	
Hydraulic Analysis and Mechanical Process Design	1
Electrical, Hazardous Area Classification, Instrumentation, and Control	3
Maintainability, Facilities Operation and Maintenance, and Vibration Analysis	1
Hazardous Materials, Design Safety Requirements, Permit Requirements and Traffic Control	1
Environmental, Stormwater, Public Impacts and Regulatory Requirements	1
Implementation Plan and Construction Sequencing	1

2.4.3 DESIGN MEMO WORKSHOPS

A. CONSULTANT shall hold workshops to present and review the Design Memos as required in **Exhibit 5 - Workshop and Meeting Requirements**.

2.4.4 PDR REVIEW WORKSHOPS

A. CONSULTANT shall hold the following workshops to review the draft Preliminary Design Report as required in **Exhibit 5 - Workshop and Meeting Requirements**:

1. Draft PDR Presentation Workshop
2. Draft PDR Review Workshop
3. PDR Validation Workshop

2.4.5 MAINTAINABILITY WORKSHOPS

A. A maintainability workshop shall be held after draft floor plans have been developed to:

1. Review the working space around equipment, accessibility requirements, specific activities required to be performed by maintenance staff, ease of servicing for equipment and devices, means to removing equipment from the point of installation to a location outside the facility, pump placement, and vibration minimization.
2. The workshop shall be used to develop a set of project maintainability design rules based on the requirements in Chapter 7 of the Engineering Design Guidelines, coordination with OC SAN staff, lessons learned from prior projects, CONSULTANT staff expertise, and manufacturer data.
3. The CONSULTANT shall research and provide the following maintainability information for the workshop:
 - a. Main sewage pumps
 - b. Operations and Maintenance (O&M) staff including staff from Maintenance Reliability and Planning must be involved in the establishment of the maintainability design rules.

B. The maintainability workshop shall be held at OC SAN's facilities and shall generally be 2 hours in length. OC SAN and CONSULTANT staff shall attend this workshop.

C. A follow up maintainability workshop shall be held at OC SAN's facilities to review the draft project maintainability design rules.

D. The project maintainability design rules shall be followed during detailed design.

E. CONSULTANT shall be responsible for completing the following tasks relative to the workshop:

1. Prepare package for the maintainability workshop participants. The package shall consist of plans, process flow diagrams, P&IDs and other information selected by CONSULTANT.
2. Prepare presentation on the project.
3. Review 3D model if applicable to the project.
4. Summarize the maintainability review workshop comments and action taken on each comment in a memorandum.
5. All comments and recommendations of the workshop and the project maintainability design rules shall be incorporated into the Maintainability Design Memo and the bid documents.

2.4.6 TECHNICAL PROGRESS MEETINGS

A. Technical Progress Meetings shall be held every 4 weeks to review various issues with OC SAN's project team. A total of 12 meetings shall be held during the Preliminary Design Phase. The CONSULTANT shall coordinate with the OC SAN Project Manager to determine what topics will be covered in what meetings, and what OC SAN and CONSULTANT team members are required for each. Assume CONSULTANT Project Manager and Project Engineer will attend every progress meeting.

2.4.7 FOCUSED MEETINGS

A. Focused meetings shall be held throughout preliminary design to discuss specific issues in detail and generate comments and direction from OC SAN staff. The following tentative list of topics may be covered in these meetings:

1. Quality control plan
2. Permits
3. OC SAN Contractor Safety Standards and other safety requirements
4. City of Newport Beach requirements
5. Instrumentation and control upgrades
6. DCS server and cabinet requirements
7. Sample P&ID; basis for equipment tag numbering
8. Sample control descriptions
9. Sample EID database
10. Sample Real IO List database
11. Data network block diagram/network connection diagram
12. I/O relocation plan
13. Electrical distribution system, system controls and the related upgrades
14. Single-line diagrams and electrical demolition
15. Construction sequencing
16. Coordination with other projects

B. Meeting lengths shall be as required to cover the topic in question. Depending on subject matter and attendees, one meeting may cover multiple subjects. CONSULTANT shall determine how many meetings will be needed to cover these topics. CONSULTANT may suggest additional topics as necessary. Supplementary meetings may be scheduled with OC SAN staff, as necessary to allow coordination between CONSULTANT and OC SAN staff.

2.4.8 COORDINATION WITH OTHER PROJECTS MEETINGS

A. The project shall be a complete and fully functional facility that is integrated with existing facilities and coordinated with other construction projects. CONSULTANT shall coordinate potential conflicts with the following adjacent projects and participate in the number of meetings indicated in the following table:

PROJECT COORDINATION MEETINGS		
PROJECT	PROJECT DESCRIPTION	COORDINATION MEETINGS
City of Newport Beach Paving Project	Paving of MacArthur Blvd	2 meetings @ 2 hours

2.4.9 STORMWATER COMPLIANCE MEETING

A. A formal meeting shall be held with OC SAN’s stormwater compliance staff to review the project scope and identify all issues during and after construction affecting compliance with stormwater regulatory requirements and OC SAN’s policies and practices.

3. PHASE 3 – DESIGN

3.0 BID DOCUMENTS

3.0.1 GENERAL

A. CONSULTANT shall provide engineering services to prepare biddable plans, technical specifications, and other Bid Documents as required based on the design concepts and criteria developed during Phase 2 – Preliminary Design. In this Scope of Work, construction documents include specifications; drawings; cable, conduit and cable tray schedules; commissioning plan materials; equipment and instrumentation database (EID); Real IO List; and bypassing plans.

3.0.2 ENGINEERING DESIGN GUIDELINE UPDATES

A. All changes in OC SAN’s Engineering Standards, OC SAN’s Design Guidelines, and/or changes in design concepts and facility layouts as a result of OC SAN comments that may occur up to transmittal of OC SAN comments on Design Submittal 2, a be incorporated into the Design by CONSULTANT with no increase in CONSULTANT’s Not-to-Exceed upper limit on fees.

3.0.3 GENERAL REQUIREMENTS AND ADDITIONAL GENERAL REQUIREMENTS

A. The following are the minimum Additional GRs topics required for this project:

- Summary of Work
- Work Sequence
- Work Restrictions
- Permits
- Environmental Restrictions and Controls
- Measurement and Payment (includes Mobilization/Demobilization)
- Shipping, Storage and Handling
- Project Control Management System (PMWeb construction management software)
- Equipment Service Manuals
- Equipment and Instrument Database (EID)
- Commissioning

- Training of OC SAN Personnel
- Hazardous Materials Mitigation and Controls
- Traffic Control

3.0.4 DESIGN SUBMITTALS

A. The CONSULTANT shall produce the following design submittals as indicated below in accordance with **Exhibit 2 - Design Requirements**. If a design submittal is eliminated, then the design submittal shall include the requirements associated with the required design submittal along with the requirements associated with the previous unchecked design submittals.

- Design Submittal 1
- Design Submittal 2
- Design Submittal 3
- Final Design Submittal
- Final Technical Plans and Specifications

B. Continuing Work After Design Submittal Submission

- CONSULTANT is expected to **continue design work** on the project while OC SAN staff reviews Design Submittal 1 and Design Submittal 2. For Design Submittal 3, CONSULTANT shall stop all design work until receipt of OC SAN comments on that submittal.
- CONSULTANT is expected to **stop design work** on the project until OC SAN staff completes the review of each Design Submittal.

3.0.5 CABLE AND CONDUIT SCHEDULE

- CONSULTANT shall put the cable and raceway schedule on the drawings. CONSULTANT may utilize an Excel spreadsheet and copy the spreadsheet onto the drawings.
- CONSULTANT shall utilize OC SAN's Microsoft Access Cable and Raceway Schedule database electronic format. See exhibit titled "Cable Conduit and Tray Schedule Database".

3.0.6 COMMISSIONING PLAN MATERIALS

- A. The CONSULTANT shall provide a commissioning plan materials in accordance **Exhibit 2 - Design Requirements**.
- B. Specification Section 01810, Commissioning and Specification Section 01810, Attachment A Commissioning Procedures
- OC SAN will prepare Section 01810
 - CONSULTANT shall prepare Section 01810 Attachment A
 - CONSULTANT shall edit Section 01810
- C. The CONSULTANT shall provide a commissioning plan FAT Narrative in accordance **Exhibit 2 - Design Requirements**.
- CONSULTANT shall prepare FAT Narrative/Commissioning Plan (for all Systems)
- D. ORT Procedures
- OC SAN will prepare ORT procedures for standard templates
 - CONSULTANT shall prepare ORT procedures using OC SAN's ORT procedure generator
 - CONSULTANT shall prepare new ORT procedures (not in standard templates)
- E. Pre-FAT Procedures
- Pre-FAT procedures not required
 - OC SAN will prepare Pre-FAT procedures
 - CONSULTANT shall prepare Pre-FAT procedures

F. FAT Procedures

- OC SAN will prepare FAT procedures
- CONSULTANT shall prepare FAT procedures
- CONSULTANT shall prepare FAT Narratives

G. RAT Procedures

- RAT procedures not required
- OC SAN will prepare RAT procedures
- CONSULTANT shall prepare RAT procedures

H. PAT Procedures

- PAT procedures not required
- OC SAN will prepare PAT procedures
- CONSULTANT shall prepare PAT procedures

3.0.7 EQUIPMENT AND INSTRUMENTATION DATABASE (EID)

- EID is not required.
- OC SAN will develop the EID in accordance **Exhibit 2 - Design Requirements.**
- CONSULTANT shall develop EID in accordance **Exhibit 2 - Design Requirements.**

3.0.8 REAL IO LIST

- Real IO List is not required.
- OC SAN will develop the Real IO List in accordance **Exhibit 2 - Design Requirements.**
- CONSULTANT shall develop the Real IO List in accordance **Exhibit 2 - Design Requirements.**

3.0.9 CONSTRUCTION SUBMITTAL ITEMS LIST

- OC SAN will develop the Construction Submittal Items List in accordance with **Exhibit 18 - Project Control Management System.**
- CONSULTANT shall develop the Construction Submittal Items List in accordance with **Exhibit 18 - Project Control Management System.**

3.0.10 TEMPORARY FACILITIES DURING CONSTRUCTION

- Temporary facilities and bypass pumping are not required.
- Temporary facilities and bypassing during construction are required, as described under the "Temporary Facilities During Construction" paragraph under the Project Elements, and shall be described in words on the drawings and technical specifications.
- Detailed plans and work sequence for temporary facilities and bypassing during construction, as described under the "Temporary Facilities During Construction" paragraph under the Project Elements.

A. CONSULTANT shall design measures for the temporary handling of flows to be implemented by the Contractor during construction considering OC SAN's goal of zero sewage spills.

B. If existing facilities such as valves, gates, stop logs, etc. are being used for shutdowns or diversions, include a plan for testing those facilities during Phase 3 – Design to verify that they will function adequately for the purpose. If testing cannot be performed, CONSULTANT shall identify the risks associated with using the facility for bypassing, along with contingency plans and mitigation measures to be implemented if they are found not function adequately during construction.

3.1 DESIGN SUPPORT DOCUMENTATION

3.1.1 DESIGN SUBMITTAL SUPPORT DOCUMENTATION

A. The CONSULTANT shall provide a Design Submittal Support Documentation in accordance **Exhibit 2 - Design Requirements.**

B. Design Information

1. CONSULTANT shall include the following material with each Design Submittal:
 - a. CONSULTANT shall maintain the Project Logs specified under Phase 2 Project Management through Phase 3. Current copies of all logs shall be included with each Design Submittal.
 - b. Written response log to OC SAN comments on the previous submittal.
 - c. CEQA and Regulatory Compliance Matrix. This matrix shall list each applicable CEQA mitigation requirement and all known permit requirements with the corresponding description of how each requirement is to be satisfied. Measures to satisfy requirements might be in the GRs, Additional GRs, particular specification requirements, or actions taken separately from the construction contract.
 - d. Calculations
 - e. Proposed list of suppliers to be named in the specifications for major equipment
 - f. Draft or final Fire Protection Reports not submitted in the previous submittal and those revised since the previous submittal.
 - g. Draft or final Field Findings Reports not submitted in the previous submittal and those revised since the previous submittal.
 - h. Equipment data sheets
 - i. Equipment catalog cuts and vendor quotations.
 - j. Commissioning Package List: The Preliminary Commissioning Package List first developed in the PDR Production Phase shall be updated in each Design Submittal and used as a starting point to develop the list of commissioning procedures.
 - k. All memos that may have been prepared since the previous submittal was delivered.

C. Facility Operation and Maintenance

- Not required.
- Update operating philosophies
- Update estimates of Operation and Maintenance staffing requirements

D. Electrical Design Documentation

- Electrical design documentation is not required.
- Updated Electrical Load Criticality Table
- Electrical Analysis Report
- Load list for all equipment
- Equipment sizing from three manufacturers for motor control centers, switchgear, transformers and power panels
- Lighting calculations
- Standby generator sizing calculations
- Uninterruptable power supply (UPS) sizing calculations
- Ductbank cable pulling tension, derating and cable tray fill calculations

E. Power System Studies

- ETAP is not required.
- Plant ETAP model for the project performed by OC SAN.
- Plant ETAP model for the project performed by CONSULTANT.
- Electrical Systems Analysis Report performed by CONSULTANT.

3.1.2 CONSTRUCTION COST ESTIMATE

A. The CONSULTANT shall provide a cost estimates for the associated design submittal indicated below in accordance with the **Engineering Design Guidelines, Chapter 15 Construction Cost Estimates.**

- PDR
- Design Submittal 1
- Design Submittal 2
- Design Submittal 3
- Final Design Submittal
- Final Technical Plans and Specifications
- Post-Bid Evaluation

3.1.3 CONSTRUCTION SCHEDULE

A. The CONSULTANT shall provide a Preliminary Construction Schedule for the associated design submittal indicated below in accordance with **Exhibit 2 - Design Requirements.**

- Construction Schedule is not Required
- Design Submittal 1
- Design Submittal 2
- Design Submittal 3
- Final Design Submittal

3.1.4 PROCUREMENT ALTERNATIVES

A. The CONSULTANT shall recommend the appropriate procurement alternatives as described in **Exhibit 2 - Design Requirements.**

- Procurement alternatives not required
- Procurement alternatives required

3.2 DESIGN ACTIVITIES

The following services shall be provided by the CONSULTANT or an appropriately qualified Subconsultant. In any case, the CONSULTANT shall be responsible for managing all subconsultants, including reviewing their work products prior to submission to OC SAN.

3.2.1 EASEMENTS, PROPERTY BOUNDARIES AND WORK AREA LIMITS

A. CONSULTANT services related to Easements, Property Boundaries and Work Area Limits on the project are specified in Phase 2 – Preliminary Design and those services shall continue during Phase 3 – Design as required. CONSULTANT shall allocate the budgeted hours between Phase 2 and Phase 3 based on when these services will be required.

3.2.2 TOPOGRAPHIC SURVEY

A. CONSULTANT services related to Topographic Survey on the project are specified in Phase 2 – Preliminary Design and those services shall continue during Phase 3 – Design as required. CONSULTANT shall allocate the budgeted hours between Phase 2 and Phase 3 based on when these services will be required.

3.2.3 UTILITY INVESTIGATION

A. CONSULTANT services related to Utility Investigation on the project are specified in Phase 2 – Preliminary Design and those services shall continue during Phase 3 – Design as required. CONSULTANT shall allocate the budgeted hours between Phase 2 and Phase 3 based on when these services will be required.

B. Final Design Submittal Utility Coordination Reviews

1. During DS3 submittal review, the CONSULTANT shall meet with outside agencies to verify any changes made by agency during the final design period and compare them with the Contract Drawings. CONSULTANT shall follow through with due diligence on utilities that do not participate in the USA program, unknown owner of a facility and/or abandoned utilities.

2. During DS3 submittal review, an on-site inspection shall be made in the project area. During the on-site inspection, a senior-level CONSULTANT representative shall walk the site accompanied by OC SAN's Project Engineer and Supervising Inspector. The CONSULTANT's representative shall be experienced in the location and identification of utilities in the field. During the on-site inspection the CONSULTANT shall document all visible features that indicate utilities within the project area and compare them with the Contract Drawings.

3.2.4 FIRE PROTECTION SERVICES

A. CONSULTANT shall secure the services of a Subconsultant to determine the fire protection requirements, prepare final plans and specifications for the selected plan and assist OC SAN in obtaining approval from the fire authority.

3.2.5 TRAFFIC CONTROL SERVICES

A. CONSULTANT shall determine traffic control requirements and prepare plans and specifications for all construction activities performed within or adjacent to the public ROW. The traffic control plans shall be approved by the AHJ by FDS. Additionally, the Traffic Control designer shall attend City and OC SAN submittal review meetings, workshops, validation meetings and focus meetings, as needed (maximum of 2 meetings with the City of Newport Beach).

3.2.6 PUBLIC RELATIONS

A. CONSULTANT services related to Public Relations on the project are specified in Phase 2 – Preliminary Design and those services shall continue during Phase 3 – Design. The CONSULTANT shall allocate the budgeted hours between the Public Relations services in Phase 2 and Phase 3 based on when these services will be required.

3.2.7 ENVIRONMENTAL DOCUMENTATION

A. CONSULTANT services related to Environmental Documentation on the project are specified in Phase 2 – Preliminary Design and those services shall continue during Phase 3 – Design. The CONSULTANT shall allocate the budgeted hours between the Environmental Documentation services in Phase 2 and Phase 3 based on when these services will be required.

3.2.8 PERMITTING ASSISTANCE

A. CONSULTANT services related to Permitting Assistance on the project are specified in Phase 2 – Preliminary Design and those services shall continue during Phase 3 – Design. CONSULTANT shall allocate the budgeted hours between the Permitting Assistance services in Phase 2 and Phase 3 based on when these services will be required.

3.2.9 PROJECT SAFETY REVIEW

A. CONSULTANT shall update Exhibit 11 – Project Safety Check List and Exhibit 12 – Full Project Safety Review Plan for review with OC SAN Risk Management during Project Safety Review Plan Workshops

B. Project Safety Workshops:

- DS1 Project Safety Review Workshop: 1 hour (held during OC SAN's review of DS1 at OC SAN)
- DS2 Project Safety Review Workshop: 1 hour (held during OC SAN's review of DS2 at OC SAN)
- DS3 Project Safety Review Workshop: 1 hour (held during OC SAN's review of DS3 at OC SAN)

C. Moderator shall be as specified for Phase 2 – Preliminary Design.

3.2.10 PROJECT MANAGEMENT

A. CONSULTANT shall be responsible for managing CONSULTANT's project execution, schedule, budget, subconsultants, and coordination with other projects. CONSULTANT services related to Project Management on the project are specified in Phase 2 – Preliminary Design and those services shall continue during Phase 3 – Design as required. CONSULTANT shall allocate the budgeted hours between Phase 2 and Phase 3 based on when these services will be required.

3.2.11 RISK MANAGEMENT

A. CONSULTANT shall provide risk management in accordance with **Exhibit 4 – Risk Management Requirements**.

3.2.12 QUALITY CONTROL

A. The CONSULTANT shall provide Quality Control requirements in accordance with **Exhibit 6 - Quality Control Requirements**.

- Independent Multi-Discipline Design Workshop is not required.
- Independent Multi-Discipline Design Workshop is required. (minimum duration of one day)

3.3 DESIGN WORKSHOPS AND MEETINGS

3.3.1 GENERAL

A. Workshop and meeting planning, requirements, agendas, and meeting minutes shall be in accordance with **Exhibit 5 - Workshop and Meeting Requirements**.

3.3.2 DESIGN PHASE WORKSHOPS

A. The focus of workshops is to review project progress to date and the technical decisions that have been made in focused meetings. CONSULTANT shall conduct the workshops listed below in Phase 3 – Design for each design submittal, except FDS. The CONSULTANT shall allow the following time for each workshop:

DESIGN PHASE WORKSHOPS	
WORKSHOP TYPE	DURATION
Design Kickoff Workshop	1 hour
Design Review Meetings	1 hour per discipline
Design Validation Meeting	2 hours

B. The following Design Review Meetings shall include the following topics, as applicable to the project:

1. Electrical
2. I&C
3. Process

4. Civil/Yard
5. Construction
6. Maintainability

3.3.3 POST-DS2 CONSTRUCTABILITY WORKSHOP

A. A constructability workshop shall be held during the DS2 submittal and shall be a three-day workshop. The constructability review is intended to provide OC SAN with an objective third-party review of the Bid Documents for effectiveness in communicating information to prospective bidders. The review shall determine if the Bid Documents have sufficient information needed to bid and construct the project and avoid misunderstandings and misinterpretations that may lead to conflict, confusion or claims during construction. This review is not a comprehensive plan check, a dimensional check or a value engineering assignment. Further, it is recognized that comments may only be given on the level of detail provided at this level of design.

B. Constructability review participants shall include highly experienced individuals from construction companies, OC SAN construction management staff and CONSULTANT construction management staff. Specialty Consultants and discipline engineers may also be included.

C. Each constructability review participant shall receive a package at least two weeks in advance. The package shall include plans and specifications, general conditions, the CPM schedule, the construction cost estimate, permits, and other pertinent information.

D. The constructability review shall be held on-site.

E. Day 1 shall start with a site visit, for the reviewers to acquaint themselves with the site conditions. After the site visit, the CONSULTANT shall make a short presentation, followed by a question and answer period. This is anticipated to take about 1/2 day. The second half of Day 1, Day 2, and the first half of day three shall be individual workdays for the Constructability Review Team. The CONSULTANT shall not attend, although one designated individual from the CONSULTANT's Design Team shall remain to answer questions and gather additional information that the Constructability Review Team might need.

F. On the afternoon of Day 3, the CONSULTANT shall return and listen to comments from the Constructability Review Team. A designated individual shall record the comments, and take notes from the workshop, to document the process.

G. Topics the Constructability Review Team must consider shall include:

1. Project consistency, discrepancies, and constructability issues
2. Contradictions, bid package strategies, and biddability issues
3. Power outages and equipment shutdowns
4. Size critical equipment requirements and constraints
5. Utility company requirements
6. Construction methods and mitigating impacts
7. Viability of equipment relocation
8. Operational requirements
9. Interim Control Plan
10. Access for maintenance
11. Access to make proper connections
12. User-friendliness and safety
13. Coordination with other projects

14. Draft Commissioning Plan
15. Public nuisance issues
16. Risk sharing
17. Construction sequencing and schedule, materials storage and work zone accessibility
18. Clarity of the Scope of Work, and interface activities
19. Impacts on existing operation
20. Access
21. Cost control
22. Partnering with Contractor
23. Other local conditions and constraints

H. The Constructability Review Team shall provide a list of comments, and the CONSULTANT shall respond to each comment, selecting those comments to be included in the final plans and specifications.

I. To facilitate the Constructability Review Workshop, CONSULTANT shall complete the following tasks:

1. Prepare package for constructability review participants. The package shall consist of detailed plans and specifications and other information selected by CONSULTANT. The package shall be mailed to participants at least one week prior to the workshop.
2. Provide for a constructability review facilitator.
3. Prepare presentation on the project for the Constructability Review Team.
4. Meet with Constructability Review Team to receive comments.
5. Provide listing of constructability review comments and action taken on each comment. (The summary report of constructability review comments shall be prepared by the Constructability Review Team.)

J. All comments and recommendations of the workshop shall be incorporated into the Bid Documents at no additional cost to OC SAN.

K. Prior to DS3, the Constructability Review Team shall also conduct an additional constructability review of the final Bid Documents to review clarity of the bid package, project completeness, and other issues, as necessary.

3.3.4 DESIGN PHASE MEETINGS

A. Technical Progress Meetings

1. Technical Progress Meetings shall be held every 4 weeks for 1 hour to review various issues with OC SAN's project team. The CONSULTANT shall coordinate with the OC SAN Project Manager to determine what topics will be covered in what meetings, and what OC SAN and CONSULTANT team members are required for each.

B. Focused Meetings

1. Focused meetings shall be held throughout preliminary design to discuss specific issues in detail and generate comments and direction from OC SAN staff. The following tentative list of topics may be covered in these meetings:

- a. Cost Estimate Review
- b. Quality control plan
- c. Process Flow diagram/Operating Philosophy (several meetings as needed)

- d. Permits
- e. OC SAN Contractor Safety Standards and other safety requirements
- f. Control concepts
- g. Instrumentation and control upgrades
- h. Sample P&ID; basis for equipment tag numbering
- i. Sample control descriptions
- j. Sample EID database
- k. Sample Real IO List database
- l. Data network block diagram/network connection diagram
- m. I/O relocation plan
- n. Electrical distribution system, system controls and the related upgrades
- o. Single-line diagrams and electrical demolition
- p. Criticality table update
- q. Construction sequencing

2. Each meeting shall generally be 1 hour in length. CONSULTANT shall determine how many meetings will be needed to cover these topics. CONSULTANT may suggest additional topics as necessary. Supplementary meetings may be scheduled with OC SAN staff, as necessary to allow coordination between the CONSULTANT and OC SAN staff.

3.3.5 CONSULTANT OFFICE TECHNICAL MEETINGS (COTMS)

A. OC SAN has found it mutually beneficial to visit the CONSULTANT offices from time to time to observe the detailed design in process, answer detailed technical questions, and establish lines of communications with CONSULTANT staff. During the Design Phase, CONSULTANT shall arrange for OC SAN staff to meet in CONSULTANT's work center and audit "over the shoulder" design reviews with CONSULTANT's staff. The reviews will be monitored by a member of the CONSULTANT's Management Team. Signification decisions will be reported to Consultants Project Manager and OC SAN's Project Manager and logged into the Decision Log. Action items will be identified.

B. The CONSULTANT shall schedule, at a minimum, the following CONSULTANT Office Technical Meetings (COTMs):

- 1. Three two-hour visits – one between each design submittal.

C. The CONSULTANT shall schedule each of the above COTMs and shall coordinate with OC SAN's Project Manager to be sure the correct personnel participate in the meetings. The CONSULTANT may propose additional, eliminate, or combine COTMs as needed to support the detailed design.

D. OC SAN may also request additional "over the shoulder" design review meetings to audit the design in other areas not listed above.

3.3.6 COORDINATION WITH OTHER PROJECTS MEETINGS

A. The project shall be a complete and fully functional facility that is integrated with existing facilities and coordinated with other construction projects. CONSULTANT shall coordinate potential conflicts with the following adjacent projects and participate in the number of meetings indicated in the following table:

PROJECT COORDINATION MEETINGS		
PROJECT	PROJECT DESCRIPTION	COORDINATION MEETINGS
City of Newport Beach Paving Project	Paving of MacArthur Boulevard	2 meetings @ 2 hours

3.3.7 COMMISSIONING TEAM MEETINGS

- A. Design phase commissioning team meetings shall be held on a monthly basis after completion of OC SAN's review DS1.
- B. Meetings will generally be 2-4 hours in length. CONSULTANT shall determine how many meetings shall be needed to cover these topics and organize the topics accordingly. CONSULTANT may suggest additional topics as necessary. Supplementary meetings may be scheduled with OC SAN staff, as necessary, to allow coordination between CONSULTANT and OC SAN staff.
- C. The Commissioning Team meetings shall cover the following subjects:
 - 1. Provide a detailed review of the proposed construction sequencing plan and make recommendations for improvements. These recommendations shall be incorporated into the plans and specifications as appropriate. Possible incentives for the Contractor to finish the project early shall be explored.
 - 2. Identify procedures, testing requirements and sequencing for commissioning.
 - 3. Develop a detailed outline of a commissioning plan based on the results of the recommended construction sequencing plan.
 - 4. Prepare testing requirements and plan to prove process performance relative to design criteria developed in the PDR. Testing shall be performed after the RAT and supervised by the CONSULTANT.
 - 5. Identify timing within the construction contract schedule when commissioning activities are required, including hold points for testing and inspection.
 - 6. Identify roles and responsibilities of the Project Manager, Resident Engineer, Inspector, Project Engineer, PCI, Engineering support, Design CONSULTANT and Contractor.
 - 7. Develop a timeline of commissioning
 - 8. Develop a commissioning specification
 - 9. Develop standard forms for testing and commissioning documentation
 - 10. Electrical, mechanical and process tie-ins
 - 11. Startup requirements and testing
 - 12. O&M training

3.3.8 PROJECT SAFETY

- A. CONSULTANT shall prepare and meet with OC SAN Risk Management personnel at PDR to review **Exhibit 11 Project Safety Checklist** and **Exhibit 12 Full Project Safety Review Plan**.
- B. CONSULTANT shall update Exhibits 11 and 12 throughout the design phases. CONSULTANT shall provide OC SAN Risk Management with the final copies of Exhibit 11 and Exhibit 12 at completion of the Design Project.

3.3.9 CONSTRUCTION SUBMITTAL ITEMS LIST MEETING

- A. Meet with OC SAN between DS2 and DS3 to review the CONSULTANT's approach to developing the project Construction Submittal Items List using **Exhibit 18 – Project Control Management System** and the CONSULTANT-provided specifications and discuss the grouping of submittals in commissioning packages and phases.

3.3.10 STORMWATER COMPLIANCE MEETING

A. A formal meeting shall be held with OC SAN's stormwater compliance staff to review the project scope and identify all issues during and after construction affecting compliance with stormwater regulatory requirements and OC SAN's policies and practices.

3.4 BID PHASE SUPPORT SERVICES

3.4.1 BID PHASE SUPPORT SERVICES

A. CONSULTANT shall provide the following bid period services:

1. Participate in the pre-bid meeting.
2. Prepare project drawing set and project specification addenda to provide clarification and resolve errors and omissions identified prior to bid opening.
3. Identify cost impacts associated with addenda changes.

3.4.2 BID EVALUATION ASSISTANCE

A. Participate in reviewing alternate equipment proposals from the Contractor, if applicable.

B. Participate in the evaluation of the submitted bids, furnish consultation and advice to OC SAN staff and assist with all the related equipment, cost, and other analyses as required to finalize the award decision.

C. If the lowest bidder exceeds the engineer's estimate by 10%, the CONSULTANT is required to conduct a confidential bid evaluation within two weeks from the bid due date. This evaluation shall include a detailed analysis of the deviation, providing reasons for the variance.

3.4.3 CONFORMED DOCUMENT PREPARATION

A. Within two weeks of the bid date, prepare conformed documents set (drawings, databases, specifications and other required materials) that incorporates the addenda. See Engineering Design Guidelines, Chapter 01, Design Guidelines – General Requirements, Section 01.5 "Preparation of Project Deliverables" for requirements as modified in Section 8 of this Scope of Work, "Project-Specific Deviations from OC SAN Design Guidelines" and the requirements of the CAD Manual).

4. PHASE 4 – CONSTRUCTION AND INSTALLATION SERVICES

Not in this Scope of Work.

5. PHASE 5 – COMMISSIONING SERVICES

Not in this Scope of Work.

6. PHASE 6 – CLOSE OUT

Not in this Scope of Work.

7. GENERAL REQUIREMENTS

7.0 GENERAL

7.0.1 OC SAN ENGINEERING DESIGN GUIDELINES AND STRATEGIC PLAN

A. CONSULTANT shall refer to and adhere to the requirements of OC SAN Contractor Safety Standards, OC SAN Engineering Design Guidelines, any deviations to the Engineering Design Guidelines listed below, and other OC SAN's Design Standards referenced therein. **Exhibit 16 - Spec Review using Microsoft Word and Teams**

B. **Exhibit 17 - OC SAN Engineering Design Guidelines and Standards – Available** online at <https://www.ocsan.gov/document-center/> is a complete set of the OC SAN Contractor Safety Standards and OC SAN Design Standards, the latest edition at the time of the design proposal stage.

C. The Engineering Guidelines define what plant design concepts/tools/methods and project management requirements shall be adhered to and in what manner they shall be used/provided by Consultants, e.g., requirements regarding design concepts, submittals, documentation details, use of OC SAN Master Specifications, and other related OC SAN Standards, etc.

D. Refer also to Section “CONSULTANT’s Responsibilities” in OC SAN Engineering Design Guidelines Chapter 01. Refer to “Master Specifications Instructions for Use” that mandates rules and conventions to be used in all OC SAN project specifications.

E. The project Scope of Work defines whether or not each specific deliverable described in the Guidelines shall be part of the project and when each task shall take place.

F. The project Scope of Work also includes requirements that supplement and/or modify the Guidelines requirements for this project.

G. The project Scope of Work and OC SAN Engineering Design Guidelines impact CONSULTANT’s project cost.

H. Except as specified in this Scope of Work, design of all facilities shall conform to the recommendations of the currently approved Master Plan for OC SAN facilities. The project shall also incorporate all applicable mitigation measures included in associated environmental documents and site-specific local requirements.

I. In addition, OC SAN will require the CONSULTANT to follow subsequent revisions of OC SAN Contractor Safety Standards, OC SAN Engineering Design Guidelines and other OC SAN Design Standards up to transmittal by OC SAN of comments on Design Submittal 2, shall be incorporated into the Design by CONSULTANT with no increase in CONSULTANT’s Not-to-Exceed upper limit on fees.

J. OC SAN may update OC SAN’s Master Specifications and/or add new OC SAN Master Specifications up to transmittal by OC SAN of comments on Design Submittal 2. The CONSULTANT shall utilize the new and/or modified Master Specifications for the DS3 submittal.

K. The CONSULTANT shall not begin editing the project specifications until the project team meets with OC SAN’s Design Standards Custodian to discuss and receive comments regarding the CONSULTANT’s proposed list of project specifications. This meeting will be used to determine which specifications are to use OC SAN’s master specifications, and where other sources will be utilized.

7.0.2 PROJECT PHASES AND TASKS

A. Project tasks and deliverables shall include the requirements described in this Scope of Work. CONSULTANT shall also refer to Appendix A of OC SAN Engineering Design Guidelines for the level of detail requirements for individual deliverables in each Phase of the project not covered in the Scope of Work.

7.0.3 CONSTRUCTION SEQUENCING AND CONSTRAINTS

A. CONSULTANT shall develop with OC SAN staff and include in the Bid Documents detailed requirements for construction sequencing and constraints. These shall ensure safe and reliable operation and maintenance of OC SAN facilities. The facilities must be kept on-line and fully operational with minimal interruptions throughout construction.

7.0.4 WORKING HOURS

A. Meetings with OC SAN staff shall be scheduled from Monday through Thursday between the hours of 8:00 AM and 4:00 PM. Any CONSULTANT staff working on-site shall conform to OC

SAN work schedules. CONSULTANT shall refer to the Engineering Design Guidelines, Chapter 01, Section 01.3.5 “CONSULTANT Inspection of Treatment Facilities” for further requirements.

7.0.5 STANDARD DRAWINGS AND TYPICAL DETAILS

A. All the details used in the project (OC SAN’s Standard Drawings and CONSULTANT-developed typical details) shall be shown on the Plans.

7.0.6 SOFTWARE

A. The CONSULTANT is expected to develop and provide the deliverables using the standard software currently approved for use by OC SAN. The standard OC SAN software includes, but is not limited to, the following:

1. Windows Professional
2. Esri software (fGDB, pGDB or shapefile formats)
3. Microsoft Internet Explorer
4. Autodesk software (AutoCAD, AutoCAD Map3D or compatible dwg file format)
5. Microsoft Office, including MS Teams
6. Maximo
7. Bluebeam Revu Extreme & Studio
8. Primavera P6 for scheduling
9. Database software as defined in the project SOW

B. Refer to Chapters 10 and 11 and Appendix A of OC SAN Engineering Design Guidelines for requirements on preparation of Criticality Tables and ETAP, Real IO List, and EID databases. Refer to OC SAN CAD Manual and to Chapter 11 and Appendix A of OC SAN Engineering Design Guidelines for requirements regarding P&ID drawings.

7.0.7 SUBMITTAL REVIEW USING BLUEBEAM

A. OC SAN has standardized on the use of Bluebeam Revu for reviewing and providing comments to PDF files. PDF files will be hosted in a Bluebeam cloud-based studio session for review. See **Exhibit 15 - Bluebeam Designer User Training** for a detailed explanation on how Bluebeam will be used to provide, validate, and close submittal review comments.

B. Prior to submitting electronic PDF files, format them as indicated in **Exhibit 14 - Bluebeam Designer Training for Submission** and “OC SAN CAD Standards Manual” prior to submission.

C. A one-hour training session on the use of Bluebeam and custom status menu will be provided by OC SAN. All CONSULTANT team members responsible for quality control and reconciliation of submittal comments shall attend.

7.0.8 WORD TRACK CHANGES

A. Specifications documents and other MS-Word based deliverables will be hosted in OC SAN Teams environment for review. The guidelines for reviewing and commenting on MS-Word files, including Specifications reviews, can be found in **Exhibit 16 - Spec Review using Microsoft Word and Teams**.

7.0.9 GIS SUBMITTALS

A. CONSULTANT shall provide the following GIS deliverables propagated from approved design submittals after the design submittal is accepted. These GIS submittals will not be reviewed or presented by CONSULTANT. The purpose is to provide project specific GIS layers that could be used to visualize interproject dependencies and conflicts.

1. Electronic Submittal

- a. Kmz files for use with Google Earth
- 2. Final PDR
 - a. Single project boundary (Polygon)
 - (1) Boundary to encompass all new facilities and existing to be modified including:
 - Buildings\Structures
 - Tunnels
 - Utilities
 - Pavement
 - Street boundary (ROW to ROW) of possible alignment
 - Easements and ROW
 - b. Structures (Polygon)
 - New structure outline
 - Additions to existing structures
 - Structure label
- 3. DS1
 - a. Project boundary - *updated from PDR*
 - b. Structures - *updated from PDR*
 - c. Utilities (Polyline)
 - (1) Utility alignment
 - (2) Known attributes (i.e. pipe diameter, material, system)
 - d. Manholes (Point)
 - (1) MH Invert Elevation
 - (2) Access information (cover diameter)
 - e. Excavation of pits (Polygon)
 - (1) Pits that will stay open for extended duration
 - (2) CIPP
 - (3) Tunnel - jacking and receiving
 - (4) All pits should be labeled
- 4. DS2, DS3, and FDS
 - a. Project boundary - updated from previous DS
 - b. Structures - updated from previous DS
 - c. Utilities - updated from previous DS
 - d. Manholes - updated from previous DS
 - e. Excavation of pits - updated from previous DS
 - f. Critical (as defined by Dig Alert) utility crossings (Point)
 - (1) Crossing of Dig Alert critical utilities
 - (2) Critical utility label
 - Natural gas

- Fuel pipeline
 - 12 kV Electrical
- (3) Metadata (source, accuracy and date of data)
- g. Asphalt (Polygon)
- (1) Asphalt to be replaced

8. PROJECT-SPECIFIC DEVIATIONS FROM OC SAN DESIGN GUIDELINES

The following Scope sections change the Engineering Design Guidelines requirements for this project and apply to ALL its Project Elements:

8.0 ENGINEERING DESIGN GUIDELINES CHAPTER 01, “DESIGN GUIDELINES – GENERAL REQUIREMENTS”

8.0.1 ENGINEERING DESIGN GUIDELINES CHAPTER 06, “MECHANICAL DESIGN”

A. Section 06.7 “Vibration Analysis for Rotating Electrical Equipment”

1. Replace the entire section with the following:

CONSULTANT shall perform a RUN evaluation for all pumping systems according to ANSI/HI 9.6.8-2014 or latest (Rotodynamic Pumps—Guideline for Dynamics of Pumping Machinery), to assess various vibration related phenomena. RUN is the general term used to denote the quantity obtained from multiplying the Risk (R) value and Uncertainty (U) value determined during the appropriate evaluation. This evaluation will help determine the relevant analysis level required to appropriately evaluate pumping machinery construction attributes and relevant site characteristics. CONSULTANT shall obtain (from the manufacturers of the rotating equipment) or calculate (based on anticipated turning speeds, operational requirements, etc.) the relevant equipment and system natural and/or excitation frequencies. These frequencies will include any effect from the various torsional, lateral, and structural behaviors of the equipment or system.

All other rotating equipment such as fans, blowers, compressors, and pumps/equipment not covered by other standards or specifications, etc. shall undergo a similar evaluation to determine relevant risk and analysis requirements to ensure project success and reliability targets are met. For these other types of rotating equipment not covered by other standards or specifications, the CONSULTANT shall propose a plan for OC SAN to approve prior to analysis being performed accordingly.

For the purpose of estimating level of effort, the Risk Value, “R”, for critical equipment that is required for continuous operation of a process system or where standard equipment is modified slightly for this application, a R-Value of 4 should be assumed. For systems dedicated to a redundant process train or where standard equipment is used, a R-Value of 2 should be assumed.

The results from the above RUN evaluation shall be used by the CONSULTANT in their subsequent design, to help provide a robust solution for the project needs. Iterations of design and equipment substitutions shall trigger additional RUN evaluations and analysis, as needed. Final equipment acceptability and commissioning shall be per ANSI/HI 9.6.4-2009 or latest (Rotodynamic Pumps—for Vibration Measurements and Allowable Values), applicable Part of ISO 10816 latest (Mechanical Vibration), ANSI/AMCA 204-05:2012 or latest (Balance Quality and Vibration Levels for Fans), ISO 1940-1:2003 or latest (Mechanical Vibration—Balance Quality Requirements for Rotors in a Constant (Rigid) State), and ISO 21940-12:2016 or latest (Mechanical Vibration—

Rotor Balancing—Procedures and Tolerances for Rotors with Flexible Behavior) as applicable. In addition, all loads, forces and moments imparted to equipment or piping, including resonance, shall be fully mitigated and all usage cases analyzed and documented per ASME 31.3-2018 or latest (Process Piping) at a minimum, and properly designed within applicable allowable stresses, etc. If there are conflicts in the standards specified, the more stringent value or condition to prevail.

9. STAFF ASSISTANCE

OC SAN staff member or designee assigned to work with CONSULTANT on the design of this project is Omeed Pour at (714) 593-7226, e-mail to: OPour@ocsan.gov.

10. EXHIBITS

Exhibit 1 - Preliminary Design Report Requirements

Exhibit 2 - Design Requirements

Exhibit 3 - Project Management Requirements

Exhibit 4 - Risk Management Requirements

Exhibit 5 - Workshop and Meeting Requirements

Exhibit 6 - Quality Control Requirements

Exhibit 7 - Design Submittal Requirements Matrix

Exhibit 8 - Project Schedule Calculation

Exhibit 9 - Deliverables Quantities

Exhibit 10 - Sample Construction Cost Estimate Formats

- a. Exhibit 10a – Sample Construction Cost Estimate Format Sample 1
- b. Exhibit 10b – Sample Construction Cost Estimate Format Sample 2-6
- c. Exhibit 10c – Sample Construction Cost Estimate Format Sample 7

Exhibit 11 - Project Safety Check List

Exhibit 12 - Full Project Safety Review Plan

Exhibit 13 - MMRP Log Template (Not Used)

Exhibit 14 - Bluebeam Designer Training for Submission

Exhibit 15 - Bluebeam Designer User Training

Exhibit 16 - Spec Review using Microsoft Word and Teams

Exhibit 17 - OC SAN Engineering Design Guidelines and Standards – Available online at <https://www.ocsan.gov/document-center/>

Exhibit 18 - Project Control Management System

- a. Attachment A – Master Construction Submittal Items List

Exhibit 19 - Project Reference Material

- b. 7-1-D MacArthur Pump Station and Force Main – 1960 (13 Sheets)
- c. 7-11-3 Abandonment of Castlerock and Dow Avenue Pump Stations & Modifications to MacArthur Pump Station – 1989 (13 Sheets)
- d. 7-68 MacArthur Force Main Improvements – 2025 (50 Sheets)

- e. 57B-NP-110 MacArthur Pump Station P&ID – 2022 (1 Sheet)
- f. FE05-37 OCSD Pump Stations Area Classification Drawing Update – 2009 (4 Sheets)
- g. J-126L Safety Improvements at Bitter Point, MacArthur, Seal Beach, Westside, and Yorba Linda Pump Stations – 2019 (18 Sheets)
- h. MacArthur Pump Station Corrosion Assessment (15 Pages)
- i. MacArthur Pump Station Visual Evaluation (19 Pages)

Exhibit 20 - CONSULTANT Outreach Presentation

Exhibit 21 – Commissioning Procedure Training

Exhibit 22 - ORT Procedure Examples

Exhibit 23 - Sample Pre-FAT Procedure

Exhibit 24 - Sample FAT Procedure

Exhibit 25 - Sample RAT Procedure

Exhibit 26 - Sample FAT Narrative

AS:op

EXHIBITS

Exhibits to Attachment A Scope of Work are considered reference material and were previously provided as part of the Request for Proposals.